

INTEGRATED TRIBAL DEVELOPMENT AGENCY : BARIPADA :

(Ph. & Fax No.(06792) 260250 e.mail - itdabaripada@rediffmail.com)

SHORT QUOTATION CALL NOTICE

No. 3441 Dt. 14.08.18

Sealed quotations are invited by the Project Administrator, ITDA, Baripada from intending reputed/registered firms/suppliers/Agencies to execute/supply the Interior and Exterior decoration of Boyanika Showroom at Sabai Crafts Building, Stadium Square, Baripada which includes for supply, fitting, fixing and installation of items as details below. The bidder should submit their bid document in sealed cover in by Registered post /Speed Post/Courier Services/by hand only. The last date of receipt of sealed quotation is on **21.08.2018** during office hours up to 5.00 P.M. the sealed quotations shall be opened by the Project Administrator, ITDA, Baripada in presence of the committee and tenderers /their authorized representative in the office chamber of the Project Administrator, ITDA, Baripada on **23.08.2018** at 11.00 A.M.

(The details of works item can be had from the office of the Project Administrator, ITDA, Baripada in person/District website www.mayurbhanj.nic.in.)

Project Administrator, ITDA, Baripada.

Terms and conditions.

1. The bidders must submit the following documents with the quotation papers positively:-
 - i. Photo copy of GST certificate.
 - ii. Photocopy of up to date I.T. return
 - iii. Photocopy of the PAN CARD (should be in his own name)
2. The bidders shall attach Earnest Money Deposit amounting to **Rs. 20,000/- (Rupees Twenty Thousand)** only in shape of Bank Draft in favour of Project Administrator, ITDA, Baripada payable at Baripada.
3. The bidders shall submit Paper cost amounting to **Rs. 2,000/- (Rupees Two Thousand)** only (Non-refundable) in shape of Bank Draft in favour of Project Administrator, ITDA, Baripada payable at Baripada.
4. The rates inclusive of all taxes for each item should be quoted with detail specifications.
5. The sealed quotations shall be received by **21.08.2018 up to 5.00 PM** during office hours (Except holidays) **through Registered Post/ Speed Post/ by courier service/ by hand (to be put in tender Box by the bidders)** at the Office of the P.A. ITDA, Baripada. The rate should be clearly mentioned on the quotation paper both in figure and word duly signed by the bidder concerned otherwise the quotation is liable to be rejected.
6. Preference will be given to the bidders having experience in successful completion of similar nature of works (for which performance certificate from competent authority must attach)

7. The quotations will be opened on **23.08.2018 at 11.00 AM** by the Purchase Committee at the office Chamber of the P.A. ITDA, Baripada.
8. The Purchase Committee shall not be bound to accept the lowest rate, but the acceptance of the quotation shall be based on the best quality of the materials. The finally accepted bidders shall strictly confirm to the approved rates and the approved sample while supplying.
9. The earnest money deposited by bidder whose quotations shall not be accepted, will be returned to them after finalization of tender on their request.
10. The finally accepted bidders shall supply articles within **30 (Thirty)** days time from the date of receipt of the supply order at their own cost in good condition at Boyanika Showroom at Sabai Crafts Building, Stadium Square, Baripada, failing which penalty will be charged as shall be determined by the Purchase Committee.
11. Order will be placed by the PA, ITDA, Baripada and quantity of articles for supply order may increase or decrease subject to availability of funds.
12. Segregation/individual item of the said quotation cannot be entertained.
13. Mandatory provision for execute the work :

1)	3D design must be submitted along with quotation basing on the approved plan.
2)	Experience certificate in interior decoration must be submitted along with quotation.
3)	Acceptance of at least one year free maintenance warrantee period.
4)	Annual Maintenance procedure and cost details for electrical and electronics items

14. The District Level Purchase Committee reserves the right to accept or to reject any or all the tenders without assigning any reason thereof.


 Project Administrator,
 ITDA, Baripada

Memo No. 3442 //ITDA, Dt. 14/8/18 18

Copy submitted to Collector & District Magistrate, Mayurbhanj-Cum-Chairman, I.T.D.A., Baripada for favour of kind information.


 Project Administrator
 I.T.D.A., Baripada.

Memo No. 3443 //ITDA, Dt. 14/8/18 18

Copy to Notice Board of I.T.D.A, Baripada / Project Administrator, ITDA Kaptipada (Udala)/ Rairangpur/ Karanjia/ Deputy Director, Horticulture, Baripada /District Welfare Officer, Mayurbhanj / General Manager, D.I.C. Mayurbhanj /Project Director, DRDA Mayurbhanj/ Addl. District Magistrate, Mayurbhanj/ District Planning Officer, Mayurbhanj Baripada / All Block Development Officers under Baripada I.T.D.A. for wide publication.

Copy to District Information Officer, NIC Baripada for information and necessary action.


 Project Administrator,
 I.T.D.A., Baripada.

List of Interior works

SL NO	DESCRIPTION	Unit	Rate to be quoted (In both word and figure)
A	INTERIOR FURNISHING		
1	Providing suspended gypsum false ceiling(India Gypsum / Saint-Gobains/ Lafarge or Equivalent) which includes G.I. perimeter channels of size 0.55mm thick (having one flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling ,screw fixed to brick wall/partition with the help of nylon sleeves and screws,at 610 mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the soffit at 1220 mm centres with ceiling angle of width 25mmx10mmx0.55mm thick fixed to soffit with G.I. cleat and steel expansion fastness. Ceiling section (Saint-Gobains or Equivalent) of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard(conforming to IS:2095-1982)is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres. screw fixing is done mechanically either with screw driver or drilling machine with suitable attachment.	Sqm	
2	Providing two coats of putty and one coat of primer and painting of Gypsum Board ceiling area with two coats of plastic emulsion paint of aproved make and quality as per the detail design and specification.	Sqm	
3	Supply and fixing of vetrified tile of 2'x2' of RAK/NITCO/KAJARIA or equivalent make all regular series inclusive of all materials for fixing and labour charges as per direction of Engineer in -charge.	Sqft.	
4	Supply, providing and fixing of black granite slab in front of entrance with cost of materials and labour charges as per direction of Engineer in -charge	Sqft.	
5	Supply and installation of M.S. heavy duty electrically operated rolling shutter with all required fittings and accessories including all charges as per direction of Engineer in -charge	Nos.	
6	Supplying and making wall cladding on wall face laminated with 1mm thick lamination board (Royal touch/ Merino or equivalent) of aproved make on 19mm block board / 12/6/3 mm ply(Century / Aeon/ Green Ply) all of waterproof quality of aproved make having fully fixed as per detail on plywood frame for walls of any length and heights along with all standard hardware ,rubber adhesive (Fevicol /royal lam/equivalent) and fitting in position as per design complete.	Sqm	
7	Supplying and making of storage rack on wall face by 19mm block board / 12/6/3 mm ply(Century / Aeon/ Alishan, Gottain, Green Ply of equivalent) all of waterproof quality of aproved make laminated with 1mm thick lamination board (Royal touch/ Merino or equivalent) of aproved make on having fully fixed as per detail on plywood frame for walls of any length and heights along with all standard hardware ,rubber adhesive (Fevicol /royal lam/equivalent) and fitting in position as per design complete.	Sqft.	
8	Supply, providing, fixing of 12mm thickness Tuffen Glass (Saint Gobain/AIS or equivalent) partition with all accessories and required hardwares as per the instruction of Engineer-in-charge with required hardware and fittings.	Sqm	
9	Supply and fixing of automated glass doors of Dorma/Godrej/Ozone or equivalent make completed with single/double sliding operation with 2 nos. radar, sensor, 1 no. light barrier and handle transmitter/receiver, programme switch, electrical operated 230 volt A/C with all required hardwares and fittings.	Each	
B	FURNITURES & DECORATIVES		
1	Providing and fixing of sales counter with 19mm block board / 12/6/3 mm ply(Century / Aeon/ Alishan, Gottain, Green Ply of equivalent) all of waterproof quality of aproved make laminated with 1mm thick lamination board (Royal touch/ Merino or equivalent) of aproved make on having fully fixed as per detail of any length and heights along with all standard hardware ,rubber adhesive (Fevicol /royal lam/equivalent) and fitting in position as per design complete.	Rft.	
2	Providing and fixing of cash counter with all accessories and all charges.	Each	
3	Supply of executive chair for cash counter of Godrej/Featherlite or equivalent make.	Each	
4	Providing of stool for customer seating arrangement.	Each	
5	Providing and stickering of handloom motives in large size venyle stickering in front of the show room.	Sqft.	
6	Provision for display arrangement and mounting of handloom motives in square bar frame work. (a) Display materials like mannequins display rings, Hangers, Display Bar, Decorative pots in hanger and other display materials.	LS	
7	Providing panneling/sealing with aluminium composite panel including all cost of materials and labour charges finished in all respect.	Sqft.	

8	Providing and fixing of LED Sign board with raised acrylic sheet lettering as approved design with all cost of materials and labour charges including installation along with stickering of different models/motives- 3 Sets	LS	
9	Supply and fixing of 6mm mirror glass inside showroom premises	Sqft.	
C	ELECTRICAL		
1	recessed wiring to light point with 1.5sqmm FR PVC Insulated single core multistrand copper Conductor of ISI marked with 20mm dia non metallic PVC flexible conduct with 6A 250V modular switch is marked and ceiling rose marked mounted on GI Box having front combined cover suitable size, G.I Box with 1.0sqmm FR PVC Single core multistrand copper conductor as earth wire including all accessories and connection (Havels/Legrend/Great White/Anchor or equivalent)		
	-do- light point Group-A	No	
	-do- light point Group-B	No	
	-do- light point Group-C	No	
2	recessed wiring to light point with 1.5sqmm FR PVC Insulated single core multistrand copper Conductor of ISI marked with 20mm dia non metallic PVC flexible conduct with 6A 250V modular switch is marked and ceiling rose marked mounted on GI Box having front combined cover suitable size, G.I Box with 1.0sqmm FR PVC Single core multistrand copper conductor as earth wire including all accessories and connection (Havels/Legrend/Great White/Anchor or equivalent) Group B	No	
3	recessed wiring to 2AMP/6AMP socket outlet with 2x1.5mm ² PVC insulated single core multistrand copper conductor of ISI marked in recess 20mm dia non metallic PVC flexible conduct with modular type switch phenolic laminated sheet suitable size ISI marked G.I. Box and earthing point with 1x1sqmm FR PVC insulated single core multistrand copper conductor for loop earthing etc, as required (Havels/Legrend/Great White/Anchor or equivalent)		
	On Existing board	No	
4	S/f G.I. Box of 12m G.I. with cover plate of recessed or in cress with suitable size of phenolic laminated sheet cover in front including providing and fixing of 15/16 Amp socket outlet and 15/16 Amp modular type switch connection painting etc as required (Havels/Legrend/Great White/Anchor or equivalent) fo A/C	No	
5	recessed wiring to Sub-main along with the following size of PVC insulated single core multistrand copper conductor ISI marked in 20mm dia non metallic heavy duty flexible conduct 1.6mm in recessed/recessed PVC conduct as required (Havels/Legrend/Great White/Anchor or equivalent)		
a	2x1.5sqmm+1x1.0sqmm	Mtr	
b	2x2.5sqmm+1x1.5sqmm	Mtr	
c	2x4sqmm+1x1.5sqmm	Mtr	
d	Dataline cable	Mtr	
e	Antina cable RJ-6	Mtr	
f	25mm sq 3.5 core cable for main supply to floor panel board	Mtr	
6	FITTINGS & FIXTURES:		
	Supply, delivery, installation and testing of following types of LED Fixtures Directly on Wall / Ceiling of Building with all accessories etc. complete assembly and making connection from the suitable point outlet as per the direction of Engineer-in-charge.		
a	20/30 Watt LED zoom type Downlighters of Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO	
b	20 watt COB type LED Downlighters Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO	
c	10 watt COB Type LED Downlighters Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make. (Sing light unit)	NO	
d	10 watt COB Type LED Downlighters Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make. (Double light unit)	NO	
e	20 watt LED track light spot light of Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO	
f	1 mtr track	NO	
g	150 watt/400 watt metal halide Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO	
h	Strip light 3watt for cove lighting Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	Mtrs.	
i	6 watt panel light Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO.	
j	3watt COB spot light Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO.	
k	Outdoor gate light Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO.	
l	20 watt Street light Havels/Surya/ Bajaj/Syska/pasolite/crompton greaves /jaquar or equivalent make.	NO.	

m	10watt glass bar decorative light of 5 feet height	NO.	
7	Supply and installation of sine wave 2 KVA UPS/invertor of Usha/Microtech/Luminous/Shakti or equivalent make machine with 2 nos. of EXIDE/Luminous/Amoran or equivalent make battery of required capacity and its accessories for power backup to sensor door, computer, limited light points.	NO.	
8	Supply and installation of 5 KVA SERVO voltage Transformer of 130V to 280V input and 230V± output of SHAKTI/ALFA or equivalent make.	NO.	
9	Supply, testing & commissioning of 30 KVA water/air cooled manual panel DG set of JAKSON/KIRLOSKAR/ MAHINDRA or equivalent for power backup to entire showroom.	NO.	
10	EARTHING		
a	Supply of materials and installation of Pipe Earth Electrode made out of 50 mm die class B G.I. Pipe of 3.0 meter long with arrangements for Fitting/ Termination of G.I. Flat / Wire with G. I. Nut Bolts & Washers including cost of Burnt Wood Charcoal, Salt, Foreign Soil, Water Pouring arrangements, Brick Masonry enclosure on top with removable RCC Cover complete with labor for excavation of pit in all kinds of Soil and Rock as required and as per direction	Nos.	
b	Supply of materials and laying on Ceiling/ Column/ Wall or Buried Under Ground including saddling & making connection at both ends and testing with following size of hot Dip Galvanized Iron Flats for Earth Termination and earth interconnection, making good the damages caused as required complete as per direction		
(i)	25 mm x 3 mm as Earthing Conductor.	Mtrs.	
c	Supply of all required materials Ashlok or Equivalent make Chemical Earthing 3 mtr. long with BF Compound, excavation & re-filling as per Direction	Nos.	
d	Earth Lead from Earth Electrode to UPS, 16 mm ² Insulated Copper Wire in GI Pipe recessed as per Direction	Mtrs.	
11	FLOOR PANEL BOARD		
	Supplying & fixing of MS Cubical type Main Panel Board of CRCA Sheet of 2 mm thick duly treated (9 Tank treatment) & powder coated with hinged door & following arrangement.		
	Incoming:	Set	
	125 Amp. Kitkat-3, 125 Amp. change over for alternative power arrangement-1, Volt meter, Ampere Meter-1 Set, Indicator lamp - 1 Set, CT-3 nos., control fuse-3 nos, busbar-1 set,		
	Outgoing:		
	40 Amp. TPN MCB-5 nos., 32 Amp. SP MCB-10 Nos., 15 Amp. Socket Switch-2 Nos.	Set	
D	AIRCONDITIONING		
1	Supply, installation, testing, commissioning of cassette type Split type-Air Conditioners of Carrier/Voltas or Equivalent aproved make including laying, sealing, tightening of ducts, Copper pipes, drain water pipe on all areas and also ancillary civil /structural works to etc as per design and instruction of Engineer in Charge of the following Tonnage.		
(i)	3 TON	No	
E	CCTV CAMERA		
1	Supply installation of CCTV camera (Vintron/CP Plus/Zebronic) or equivalent with required cable with 16 channel DVR Display monitor. IR bullet type camera, IR dome camera with full HD clarity and required accessories as per the direction of EIngineer-in-charge	Set	
F	COMPUTERIZED BILLING UNIT		
1	Supply, installation, testing, commissioning of computer billing unit consist of HP/HCL/Lenevo/Dell or equivalent PC with required accessories		
(i)	COMPUTER Complete set	Set	
	Printer		
	Bar code scanner		

G	Fire Fighting system		
(i)	Supply, installing, connecting up, testing & commissioning of the following the alarm equipment:		
a)	Smoke Detector.	No.	
b)	Response indicator	No.	
c)	Electronic Hooters (4 Watt).	No.	
d)	Manual Break Glass.	No.	
e)	2 Zone Fire Panel (AGNI).	No.	
f)	Supply and fixing of Response Indicator.	No.	
g)	Supplying and laying of 2 Core 1.5 mm2 Un-armored Cable for Fire Alarm System.	No.	
(ii)	Supply, installation, testing and commissioning of following fire extinguishing equipments:	No.	
a)	CO2 Fire Extinguishers 4.5 kg.	No.	
b)	ABC type fire extinguisher 2 kg.	No.	
C)	ABC type fire extinguisher 4 kg.	No.	
H	3D view for the project	1 job	


 T-7/8/18
Project Administrator
I.T.D.A., Baripada