

OFFICE OF THE PANCHAYAT SAMITI: JASHIPUR

At/PO- Jashipur, Dist:- Mayurbhanj, Odisha-757091
Tel/Fax- 06797-232435, E-Mail- ori-jashipur@nic.in

No. 197 // Dated. 22.1.2025 //

1st Corrigendum Notice to Bid Identification No.01/BDO, Jashipur Dated.09.01.2025 regarding construction of 06(Six) nos of GPLF Buildings with Market Complex

Due to unavoidable circumstances, the following Amendment has been made in Bid Identification No.01/BDO, Jashipur Dated.09.01.2025.

1. Last date and time of receipt of bid documents is extended till **03.02.2025 (up to 5.00 PM)** in **Office of the Block Development Officer, Jashipur.**
2. The date and time of opening of bid documents is rescheduled on **04.02.2025 at 11 A.M.**
3. The mode of receipt of tender paper is through **Speed Post /Registered Post only. No tender paper will be received by hand service.**
4. **Revised Bill of Quantity (BOQ) will be made available at District NIC website i.e. www.mayurbhanj.odisha.gov.in from Dt:24.01.2025 to Dt: 03.02.2025 (up to 05.00 PM) (on working days only).** All interested bidders are requested to send their bid documents in revised BOQ format duly filled in all respect along with all other documents related to tender in sealed cover, otherwise Tender paper is liable for rejection.

All other terms and conditions remain unaltered.

Block Development Officer,
Jashipur

Block Development Officer
Jashipur

Memo No. 198 // Dated. 22.1.2025 //


Copy submitted to the Collector & District Magistrate, Mayurbhanj/ Superintendent of Police, Baripada/CDO-cum-EO, Zilla Parishad, Mayurbhanj/CDM & PHO, Mayurbhanj/Chief Engineer & Basin Manager, B.S.&B. Basin, Laxmiposi/Superintending Engineer, Irrg. Circle, Baripada/ Executive Engineer, M.I. Division, Baripada, Superintending Engineer/Executive Engineer, (R&B) Division, Baripada/Rairangpur/N.H. Division, Baripada/Executive Engineer, Mayurbhanj Irrigation Division, Baripada/ Executive Engineer, R.W.S&S Division, Baripada/ Superintending Engineer, RWD, Baripada/Rairangpur/Karanjia/Executive Officer, Baripada Municipality for favour of kind information and wide circulation of Corrigendum Notice.

Block Development Officer,
Jashipur

Block Development Officer
Jashipur

Memo No. 199 // Dated. 22.1.2025 //

Copy submitted to the Sub-collector, Panchpir, Karanjia/BDO, Karanjia, Sukruli, Raruan and Thakurmunda of Mayurbhanj District/ All Govt. Offices of Mayurbhanj District with request to display the Corrigendum Notice on their Notice Board for wide publication.


Block Development Officer,
Jashipur
22.1.25
Block Development Officer
Jashipur

Memo No. 200 // Dated. 22.1.2025 //

Copy submitted to the Sub-Divisional Police Officer, Karanjia for favour of information and necessary action with request to provide adequate police personnel to Jashipur Block on the day of opening of tender papers i.e. on 04.02.2025.

Copy forwarded to the Inspector-in-Charge, Jashipur PS for information and necessary follow up action.


Block Development Officer,
Jashipur
22.1.25
Block Development Officer
Jashipur

Memo No. 201 // Dated. 22.1.2025 //

Copy to All tender committee members for information and necessary action. They are requested to remain present during opening of the tender papers as per fixed date, venue and time.


Block Development Officer,
Jashipur
22.1.25
Block Development Officer
Jashipur

Memo No. 202 // Dated. 22.1.2025 //

Copy to Office Notice Board for wide publicity of Corrigendum Notice.
Copy to Tender file for office record.
Copy to C.P. of Jashipur Block with direction to assist for uploading the Corrigendum Notice and Revised BOQ at NIC, Mayurbhanj by 24.01.2025.


Block Development Officer,
Jashipur
22.1.25
Block Development Officer
Jashipur

REVISED BOQ

NAME OF WORK :- CONSTRUCTION OF G+1F BUILDING WITH MARKET COMPLEX AT JASTAKUNAR

Sl. No.	Discreption of Item	Quantity	Unit	Rate	Amount in Rs
1	Earth work excavation of foundation in Ordinary soil within initial lead & lift including rough dressing breaking cliods to maximum 5cm to 7cm size and laying in layers not exceeding 0.30m depth	62.96	Cum	270.90	Rs.17,055.00
2	Filling in foundation and plinth with sand well watered and rammed including cost conveyance and royalty etc. complete.	59.65	Cum	873.70	Rs.52,113.00
3	Cement Concrete (1:3:6) with 4cm size hard granite C B metal in Foundation and Plinth.	27.97	Cum	7575.50	Rs.211,892.00
4	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
	Ground Floor	52.13	Cum	7393.90	Rs.385,461.00
5	Supplying fitting and placing uncoated HYSD bar reinforcement complete asper drawing and technical specification.				
	Ground Floor	52.13	Qntls	8822.70	Rs.459,948.00
6	Rigid and smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete				
	i) RCC beams,columns,girders and bressmer				
A	Ground Floor	138.98	Sqm	1189.30	Rs.165,295.00
	ii) RCC foundation,plinth bands and footing bases of columns mass concrete pre cast slabs				
A	Ground Floor	30.99	Sqm	247.50	Rs.7,671.00
	iii) RCC Lintels				
A	Ground Floor	25.20	Sqm	570.30	Rs.14,374.00
	iv) RCC floor, Roof slab,landings,balconies,projecting sunshades and chajjas				
A	Ground Floor	33.39	Sqm	755.00	Rs.25,209.00
7	Fly ash Brick masonry in cement mortar (1:6) in Foundation and Plinth and superstructure etc. complete.				
A	Ground Floor				
	i) Infoundation	16.85	Cum	5905.20	Rs.99,502.00
	ii) Superstructure	39.63	Cum	5943.50	Rs.235,553.00
8	16mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	318.07	Sqm	295.40	Rs.93,958.00
9	12mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	108.76	Sqm	208.40	Rs.22,665.00
10	6mm thick cement plaster (1:4) Over R.C.C. Surface including cost conveyance and royalty etc. complete.				
A	Ground Floor	116.72	Sqm	220.70	Rs.25,760.00
11	Supplying,fitting and fixing of M.S. Door and Window including all labours T&P etc. complete				
A	Ground Floor	921.25	Kg	152.33	Rs.140,332.00
12	Painting two coats with any approved paint including cost of primer,paints etc complete.				
A	Ground Floor	42.08	Sqm	182.00	Rs.7,659.00
13	20mm thick grading plaster (1:6) over rcc roof slab etc complete				
A	Ground Floor	74.83	Sqm	365.70	Rs.27,365.00
14	Finishing wall with Cement Based Wall Putty of approved make and finished smooth and even surface to receive painting including all cost				
A	Ground Floor	382.14	Sqm	83.90	Rs.32,061.00
15	Priming one coat with any approved primer including cost of primer including cost of primer,paints etc complete.				

	A	Ground Floor	581.51	Sqm	73.60	Rs.42,799.00
16		Wall painting two coats with plastic emulsion paint of approved shade on new work to give an even shade, etc complete				
	A	Ground Floor	433.09	Sqm	102.80	Rs.44,522.00
17		Providing and applying paint over external plastered surfaces with 2 coats of weather seal coat of approved quality and shades using the required quality and shades using the required quantity of				
	A	Ground Floor	108.76	Sqm	96.00	Rs.10,441.00
18		Fixing tiles in floors tread or step landind on 25mm thick bed C.M.(1:1) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete				
	A	Ground Floor	112.85	Sqm	1195.50	Rs.134,918.00
19		Fixing tiles in dados, skirting & rise of step on 12mm thick bed of CM (1:3) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete excluding cost				
	A	Ground Floor	41.63	Sqm	1320.50	Rs.54,975.00
20		Supplying, fitting & fixing of Chequered tiles in floors of approved make laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with slurry including cost of all	17.65	Sqm	676.80	Rs.11,946.00
21		Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless	12.19	Rmt	3508.85	Rs.42,780.00
22		Add for Work Contingency @ 1%				Rs 23,66,254.00
23		Add for ... 13% (C.C.) @ ...				Rs. 23,66,254.00


Junior Engineer
Jashipur Block


Asst. Executive Engineer
Jashipur Block


Block Development Officer
Jashipur Block
Jashipur

I am willing to execute the Work

- 1) _____ % Excess (In Words _____)
 2) _____ % Less (In Words _____)

Signature of the Contractor

Approved

Block Development Officer
Jashipur

Sold for the work construction of the GPLF Building with Market Complex at Astakuanr on realization of Rs.6000/- towards cost of Tender Paper in shape of Demand Draft.

Dt. _____


Block Development Officer
Jashipur
Block Development Officer
Jashipur

REVISED BOQ

NAME OF WORK :- CONSTRUCTION OF GPLF BUILDING WITH MARKET COMPLEX AT BAREHIPANI G.P.

Sl. No.	Discreption of Item	Quantity	Unit	Rate	Amount in Rs
1	Earth work excavation of foundation in Ordinary soil within initial lead & lift including rough dressing breaking clods to maximum 5cm to 7cm size and laying in layers not exceeding 0.30m depth	62.96	Cum	270.90	Rs.17,055.00
2	Filling in foundation and plinth with sand well watered and rammed including cost conveyance and royalty etc. complete.	59.65	Cum	873.70	Rs.52,113.00
3	Cement Concrete (1:3:6) with 4cm size hard granite C B metal in Foundation and Plinth.	27.97	Cum	7374.80	Rs.206,278.00
4	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
	Ground Floor	52.13	Cum	7205.70	Rs.375,650.00
5	Supplying fitting and placing uncoated HYSD bar reinforcement complete asper drawing and technical specification.				
	Ground Floor	52.13	Qntls	8822.70	Rs.459,948.00
6	Rigid and smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete				
	i) RCC beams,columns,girders and bressmer				
A	Ground Floor	138.98	Sqm	1189.30	Rs.165,295.00
	ii) RCC foundation,plinth bands and footing bases of columns mass concrete pre cast slabs				
A	Ground Floor	30.99	Sqm	247.50	Rs.7,671.00
	iii) RCC Lintels				
A	Ground Floor	25.20	Sqm	570.30	Rs.14,374.00
	iv) RCC floor,Roof slab,landings,balconies,projecting sunshades and chajjas				
A	Ground Floor	33.39	Sqm	755.00	Rs.25,209.00
7	Fly ash Brick masonry in cement mortar (1:6) in Foundation and Plinth and superstructure etc. complete.				
A	Ground Floor				
	i) Infoundation	16.85	Cum	5792.80	Rs.97,608.00
	ii) Superstructure	39.63	Cum	5831.20	Rs.231,102.00
8	16mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	318.07	Sqm	292.90	Rs.93,163.00
9	12mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	108.76	Sqm	206.30	Rs.22,436.00
10	6mm thick cement plaster (1:4) Over R.C.C. Surface including cost conveyance and royalty etc. complete.				
A	Ground Floor	116.72	Sqm	219.60	Rs.25,632.00
11	Supplying,fitting and fixing of M.S. Door and Window including all labours T&P etc. complete				
A	Ground Floor	921.25	Kg	152.33	Rs.140,332.00
12	Painting two coats with any approved paint including cost of primer,paints etc complete.				
A	Ground Floor	42.08	Sqm	182.00	Rs.7,659.00
13	20mm thick grading plaster (1:6) over rcc roof slab etc complete				
A	Ground Floor	74.83	Sqm	362.80	Rs.27,148.00
14	Finishing wall with Cement Based Wall Putty of approved make and finished smooth and even surface to receive painting including all cost				
A	Ground Floor	382.14	Sqm	83.90	Rs.32,061.00

15	Priming one coat with any approved primer including cost of primer,paints etc. complete				
	A Ground Floor	581.51	Sqm	73.60	Rs.42,799.00
16	Wall painting two coats with plastic emulsion paint of approved shade on new work to give an even shade, etc. complete				
	A Ground Floor	433.09	Sqm	102.80	Rs.44,522.00
17	Providing and applying paint over external plastered surfaces with 2 coats of weather seal coat of approved quality and shades using the required quality				
	A Ground Floor	108.76	Sqm	96.00	Rs.10,441.00
18	Fixing tiles in floors tread or step landind on 25 mm thick bed C.M.(1:1) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete				
	A Ground Floor	112.85	Sqm	1188.60	Rs.134,139.00
19	Fixing tiles in dados, skirting & rise of step on 12 mm thick bed of CM(1:3) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete				
	A Ground Floor	41.63	Sqm	1314.40	Rs.54,721.00
20	Supplying,fitting & fixing of Chequered tiles in floors of approved make laid on 20 mm thick cement mortar(1:4) (1 cement:4 course sand) and filling joints with slurry including cost of all materials,labour T & P etc. required for the work all complete as per direction of the Engineer-in-charge	17.65	Sqm	669.80	Rs.11,823.00
21	Supplying ,fitting and fixing of Stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32 mm x 2 mm @0.90 mtr. C/C and stainless square pipe bracing of size 2 mm x 32 mm x 2 mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost,conveyance, taxes of all materials,labour, T & P etc. required for the complete in all respect Data for 3.26 Rmt.	12.19	Rmt	3508.85	Rs.42,780.00
				Total	Rs.23,41,959.00

(Rupees Twenty Three Lakh Forty One Thousand Nine Hundred Fifty Nine) only


Signature of AEE


Block Development Officer
Jashipur

I am willing to execute the work

- 1) _____% Excess (In words _____)
- 2) _____% Less (In words _____)

Signature of the Contractor

Approved

Block Development Officer
Jashipur

Sold for the work Construction of the GPLF Building with Market Complex at Barerhipani on realization of Rs.6000/- towards cost of Tender Paoper in shape of Demand Draft

Dt _____


Block Development Officer
Jashipur
Block Development Officer
Jashipur


REVISED BOQ

NAME OF WORK :- CONSTRUCTION OF GPLF BUILDING WITH MARKET COMPLEX AT DURDURA

Sl. No.	Discreption of Item	Quantity	Unit	Rate	Amount in Rs
1	Earth work excavation of foundation in Ordinary soil within initial lead & lift including rough dressing breaking cliods to maximum 5cm to 7cm size and laying in layers not exceeding 0.30m depth	62.96	Cum	270.90	Rs.17,055.00
2	Filling in foundation and plinth with sand well watered and rammed including cost conveyance and royalty etc. complete.	59.65	Cum	873.70	Rs.52,113.00
3	Cement Concrete (1:3:6) with 4cm size hard granite C B metal in Foundation and Plinth.	27.97	Cum	6817.30	Rs.190,685.00
4	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
	Ground Floor	52.13	Cum	6683.10	Rs.348,405.00
5	Supplying fitting and placing uncoated HYSD bar reinforcement complete asper drawing and technical specification.				
	Ground Floor	52.13	Qntls	8822.70	Rs.459,948.00
6	Rigid and smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete				
	i) RCC beams,columns,girders and bressmer				
A	Ground Floor	138.98	Sqm	1189.30	Rs.165,295.00
	ii) RCC foundation,plinth bands and footing bases of columns mass concrete pre cast slabs				
A	Ground Floor	30.99	Sqm	247.50	Rs.7,671.00
	iii) RCC Lintels				
A	Ground Floor	25.20	Sqm	570.30	Rs.14,374.00
	iv) RCC floor,Roof slab,landings,balconies,projecting sunshades and chajjas				
A	Ground Floor	33.39	Sqm	755.00	Rs.25,209.00
7	Fly ash Brick masonry in cement mortar (1:6) in Foundation and Plinth and superstructure etc. complete.				
A	Ground Floor				
	i) Infoundation	16.85	Cum	5661.10	Rs.95,388.00
	ii) Superstructure	39.63	Cum	5699.50	Rs.225,882.00
8	16mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	318.07	Sqm	285.40	Rs.90,777.00
9	12mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	108.76	Sqm	200.10	Rs.21,762.00
10	6mm thick cement plaster (1:4) Over R.C.C. Surface including cost conveyance and royalty etc. complete.				
A	Ground Floor	116.72	Sqm	216.50	Rs.25,270.00
11	Supplying,fitting and fixing of M.S. Door and Window including all labours T&P etc. complete				
A	Ground Floor	921.25	Kg	152.33	Rs.140,332.00
12	Painting two coats with any approved paint including cost of primer,paints etc complete.				
A	Ground Floor	42.08	Sqm	182.00	Rs.7,659.00
13	20mm thick grading plaster (1:6) over rcc roof slab etc complete				
A	Ground Floor	74.83	Sqm	354.00	Rs.26,490.00
14	Finishing wall with Cement Based Wall Putty of approved make and finished smooth and even surface to receive painting including all cost				
A	Ground Floor	382.14	Sqm	83.90	Rs.32,061.00
15	Priming one coat with any approved primer including cost of primer including cost of primer,paints etc complete.				

	A	Ground Floor	581.51	Sqm	73.60	Rs.42,799.00
16		Wall painting two coats with plastic emulsion paint of approved shade on new work to give an even shade, etc complete				
	A	Ground Floor	433.09	Sqm	102.80	Rs.44,522.00
17		Providing and applying paint over external plastered surfaces with 2 coats of weather seal coat of approved quality and shades using the required quality and shades using the required quantity of				
	A	Ground Floor	108.76	Sqm	96.00	Rs.10,441.00
18		Fixing tiles in floors tread or step landind on 25mm thick bed C.M.(1:1) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete				
	A	Ground Floor	112.85	Sqm	1160.60	Rs.130,979.00
19		Fixing tiles in dados, skirting & rise of step on 12mm thick bed of CM (1:3) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete excluding cost				
	A	Ground Floor	41.63	Sqm	1288.90	Rs.53,660.00
20		Supplying, fitting & fixing of Chequered tiles in floors of approved make laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with slurry including cost of all	17.65	Sqm	641.80	Rs.11,328.00
21		Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless	12.19	Rmt	3508.85	Rs.42,780.00
					Total	Rs.2,282,885.00


Junior Engineer
Jashipur Block


Asst. Executive Engineer
Jashipur Block


Block Development officer
Jashipur Block
Jashipur

I am willing to execute the Work

- 1) _____ % Excess (In Words _____)
2) _____ % Less (In Words _____)

Signature of the Contractor

Approved

Block Development Officer
Jashipur
Jashipur

Sold for the work construction of the GPLF Building with Market Complex at Durdura on realization of Rs.6000/- towards cost of Tender Paper in shape of Demand Draft.
Dt. _____


Block Development Officer
Jashipur
Block Development Officer
Jashipur

REVISED BOQ

NAME OF THE WORK :- CONSTRUCTION OF GPLF BUILDING WITH MARKET COMPLEX AT GUDGUDIA.

Sl. No.	Discreption of Item	Quantity	Unit	Rate	Amount in Rs
1	Earth work excavation of foundation in Ordinary soil within initial lead & lift including rough dressing breaking clods to maximum 5cm to 7cm size and laying in layers not exceeding 0.30m depth etc. (Data for 100 cum)	62.96	Cum	270.90	Rs.17,055.00
2	Filling in foundation and plinth with sand well watered and rammed including cost conveyance and royalty etc. complete.	59.65	Cum	807.90	Rs.48,188.00
3	Cement Concrete (1:3:6) with 4cm size hard granite C B metal in Foundation and Plinth.	27.97	Cum	6982.30	Rs.1,95,300.00
4	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
	Ground Floor	52.13	Cum	6837.80	Rs.3,56,470.00
5	Supplying fitting and placing uncoated HYSD bar reinforcement complete asper drawing and technical specification.				
	Ground Floor	52.13	Qntls	8822.70	Rs.4,59,948.00
6	Rigid and smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete				
	i) RCC beams,columns,girders and bressmer				
A	Ground Floor	138.98	Sqm	1189.30	Rs.1,65,295.00
	ii) RCC foundation,plinth bands and footing bases of columns mass concrete pre cast slabs				
A	Ground Floor	30.99	Sqm	247.50	Rs.7,671.00
	iii) RCC Lintels				
A	Ground Floor	25.20	Sqm	570.30	Rs.14,374.00
	iv) RCC floor, Roof slab,landings,balconies,projecting sunshades and chajjas				
A	Ground Floor	33.39	Sqm	755.00	Rs.25,209.00
7	Fly ash Brick masonry in cement mortar (1:6) in Foundation and Plinth and superstructure etc. complete.				
A	Ground Floor				
	i) Infoundation	16.85	Cum	5621.50	Rs.94,721.00
	ii) Superstructure	39.63	Cum	5659.90	Rs.2,24,313.00
8	16mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	318.07	Sqm	288.20	Rs.91,668.00
9	12mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	108.76	Sqm	202.40	Rs.22,012.00
10	6mm thick cement plaster (1:4) Over R.C.C. Surface including cost conveyance and royalty etc. complete.				
A	Ground Floor	116.72	Sqm	217.70	Rs.25,410.00
11	Supplying,fitting and fixing of M.S. Door and Window including all labours T&P etc. complete				
A	Ground Floor	921.25	Kg	152.33	Rs.1,40,332.00
12	Painting two coats with any approved paint including cost of primer,paints etc complete.				
A	Ground Floor	42.08	Sqm	182.00	Rs.7,659.00
13	20mm thick grading plaster (1:6) over rcc roof slab etc complete				
A	Ground Floor	74.83	Sqm	357.30	Rs.26,737.00
14	Finishing wall with Cement Based Wall Putty of approved make and finished smooth and even surface to receive painting including all cost				
A	Ground Floor	382.14	Sqm	83.90	Rs.32,061.00

15	Priming one coat with any approved primer including cost of primer including cost of primer, paints etc complete.				
	A Ground Floor	581.51	Sqm	73.60	Rs.42,799.00
16	Wall painting two coats with plastic emulsion paint of approved shade on new work to give an even shade, etc complete				
	A Ground Floor	433.09	Sqm	102.80	Rs.44,522.00
17	Providing and applying paint over external plastered surfaces with 2 coats of weather seal coat of approved quality and shades using the required quality and shades using the required quantity of paint etc				
	A Ground Floor	108.76	Sqm	96.00	Rs.10,441.00
18	Fixing tiles in floors tread or step landing on 25mm thick bed of C.M.(1:1) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete excluding cost of tiles for 10 Sqm				
	A Ground Floor	112.85	Sqm	1166.20	Rs.1,31,611.00
19	Fixing tiles in gados, skirting & rise or step on 12mm thick bed of CM (1:3) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete excluding cost of tiles for 10 Sqm				
	A Ground Floor	41.63	Sqm	1293.60	Rs.53,855.00
20	Supplying, fitting & fixing of Chequered tiles in floors of approved make laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with slurry including cost of all materials, labour T&P etc required for the work all complete as per direction of the Engineer-in-charge	17.65	Sqm	647.50	Rs.11,429.00
21	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour.	12.19	Rmt	3508.85	Rs.42,780.00
				Total	Rs.22,91,860.00

(Twenty one items only.)

(Rupees Twenty two Lakhs ninety one thousands eight hundred sixty)only.

Approved


Block Development officer,
Jashipur Block
Jashipur


AEE

I am willing to execute the Work

- 1) _____ % Excess (In Words _____)
2) _____ % Less (In Words _____)

Signature of the Contractor

Approved


Block Development Officer
Jashipur
Jashipur

Sold for the work construction of the GPLF Building with Market Complex at Gudgudia on realization of Rs.6000/- towards cost of Tender Paper in shape of Demand Draft.

Dt. _____


Block Development Officer
Jashipur
Block Development Officer
Jashipur

REVISED BOQ

NAME OF THE WORK :- CONSTRUCTION OF GPLF OFFICE BUILDING WITH MARKET COMPLEX AT JASHIPUR.

Sl. No.	Discreption of Item	Quantity	Unit	Rate	Amount in Rs
1	Earth work excavation of foundation in Ordinary soil within initial lead & lift including rough dressing breaking clods to maximum 5cm to 7cm size and laying in layers not exceeding 0.30m depth etc. (Data for 100 cum)	62.96	Cum	270.90	Rs.17,055.00
2	Filling in foundation and plinth with sand well watered and rammed including cost conveyance and royalty etc. complete.	59.65	Cum	873.70	Rs.52,113.00
3	Cement Concrete (1:3:6) with 4cm size hard granite C B metal in Foundation and Plinth.	27.97	Cum	6601.80	Rs.1,84,657.00
4	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
	Ground Floor	52.13	Cum	6481.10	Rs.3,37,875.00
5	Supplying fitting and placing uncoated HYSD bar reinforcement complete asper drawing and technical specification.				
	Ground Floor	52.13	Qntls	8822.70	Rs.4,59,948.00
6	Rigid and smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete.				
	i) RCC beams,columns,girders and bressmer				
A	Ground Floor	138.98	Sqm	1189.30	Rs.1,65,295.00
	ii) RCC foundation,plinth bands and footing bases of columns mass concrete pre cast slabs				
A	Ground Floor	30.99	Sqm	247.50	Rs.7,671.00
	iii) RCC Lintels				
A	Ground Floor	25.20	Sqm	570.30	Rs.14,374.00
	iv) RCC floor,Roof slab,landings,balconies,projecting sunshades and chajjas				
A	Ground Floor	33.39	Sqm	755.00	Rs.25,209.00
7	Fly ash Brick masonry in cement mortar (1:6) in Foundation and Plinth and superstructure etc. complete.				
A	Ground Floor				
	i) Infoundation	16.85	Cum	5489.30	Rs.92,494.00
	ii) Superstructure	39.63	Cum	5527.70	Rs.2,19,074.00
8	16mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	318.07	Sqm	283.70	Rs.90,236.00
9	12mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	108.76	Sqm	198.70	Rs.21,610.00
10	6mm thick cement plaster (1:4) Over R.C.C. Surface including cost conveyance and royalty etc. complete.				
A	Ground Floor	116.72	Sqm	215.80	Rs.25,188.00
11	Supplying,fitting and fixing of M.S. Door and Window including all labours T&P etc. complete				
A	Ground Floor	921.25	Kg	152.33	Rs.1,40,332.00
12	Painting two coats with any approved paint including cost of primer,paints etc complete.				
A	Ground Floor	42.08	Sqm	182.00	Rs.7,659.00
13	20mm thick grading plaster (1:6) over rcc roof slab etc complete				
A	Ground Floor	74.83	Sqm	352.10	Rs.26,348.00
14	Finishing wall with Cement Based Wall Putty of approved make and finished smooth and even surface to receive painting including all cost				
A	Ground Floor	382.14	Sqm	83.90	Rs.32,061.00

15	Priming one coat with any approved primer including cost of primer,paints etc. complete				
	A Ground Floor	581.51	Sqm	73.60	Rs.42,799.00
16	Wall painting two coats with plastic emulsion paint of approved shade on new work to give an even shade, etc. complete				
	A Ground Floor	433.09	Sqm	102.80	Rs.44,522.00
17	Providing and applying paint over external plastered surfaces with 2 coats of weather seal coat of approved quality and shades using the required quality				
	A Ground Floor	108.76	Sqm	96.00	Rs.10,441.00
18	Fixing tiles in floors tread or step landind on 25 mm thick bed C.M.(1:1) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete				
	A Ground Floor	112.85	Sqm	1161.90	Rs.131,126.00
19	Fixing tiles in dados, skirting & rise of step on 12 mm thick bed of CM(1:3) jointed with neat cement slurry mixed with pigment match the shades including rubbing & polishing complete				
	A Ground Floor	41.63	Sqm	1290.80	Rs.53,739.00
20	Supplying,fitting & fixing of Chequered tiles in floors of approved make laid on 20 mm thick cement mortar(1:4) (1 cement:4 course sand) and filling joints with slurry including cost of all materials,labour T & P etc. required for the work all complete as per direction of the Engineer-in-charge	17.65	Sqm	643.20	Rs.11,353.00
21	Supplying ,fitting and fixing of Stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32 mm x 2 mm @0.90 mtr. C/C and stainless square pipe bracing of size 2 mm x 32 mm x 2 mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost,conveyance, taxes of all materials,labour, T & P etc. required for the complete in all respect Data for 3.26 Rmt.	12.19	Rmt	3508.85	Rs.42,780.00
				Total	Rs.22,55,959.00

(Rupees Twenty Two Lakh Fifty Five Thousand Nine Hundred Fifty Nine) only


Signature of AEE


Block Development Officer
Jashipur

I am willing to execute the work

- 1) _____ % Excess (In words _____)
2) _____ % Less (In words _____)

Approved

Signature of the Contractor


Block Development Officer
Jashipur

Sold for the work construction of the GPLF Building with Market Complex at Jashipur on realization of Rs.6000/- towards cost of Tender Paoper in shape of Demand Draft

Dt _____


Block Development Officer
Jashipur
Block Development Officer
Jashipur

REVISED BOQ

NAME OF WORK :- CONSTRUCTION OF GPLF BUILDING WITH MARKET COMPLEX AT PODAGARH

Sl. No.	Discreption of Item	Quantity	Unit	Rate	Amount in Rs
1	Earth work excavation of foundation in Ordinary soil within initial lead & lift including rough dressing breaking cliods to maximum 5cm to 7cm size and laying in layers not exceeding 0.30m depth	62.96	Cum	270.90	Rs.17,055.00
2	Filling in foundation and plinth with sand well watered and rammed including cost conveyance and royalty etc. complete.	59.65	Cum	1005.20	Rs.59,957.00
3	Cement Concrete (1:3:6) with 4cm size hard granite C B metal in Foundation and Plinth.	27.97	Cum	6995.70	Rs.195,675.00
4	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying				
	Ground Floor	52.13	Cum	6850.30	Rs.357,122.00
5	Supplying fitting and placing uncoated HYSD bar reinforcement complete asper drawing and technical specification.				
	Ground Floor	52.13	Qntls	8822.70	Rs.459,948.00
6	Rigid and smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete				
i)	RCC beams,columns,girders and bressmer				
A	Ground Floor	138.98	Sqm	1189.30	Rs.165,295.00
ii)	RCC foundation,plinth bands and footing bases of columns mass concrete pre cast slabs				
A	Ground Floor	30.99	Sqm	247.50	Rs.7,671.00
iii)	RCC Lintels				
A	Ground Floor	25.20	Sqm	570.30	Rs.14,374.00
iv)	RCC floor,Roof slab,landings,balconies,projecting sunshades and chajjas				
A	Ground Floor	33.39	Sqm	755.00	Rs.25,209.00
7	Fly ash Brick masonry in cement mortar (1:6) in Foundation and Plinth and superstructure etc. complete.				
A	Ground Floor				
i)	Infoundation	16.85	Cum	5650.70	Rs.95,213.00
ii)	Superstructure	39.63	Cum	5689.00	Rs.225,466.00
8	16mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	318.07	Sqm	287.10	Rs.91,318.00
9	12mm thick cement plaster (1:6) for brick work including cost conveyance and royalty etc. complete.				
A	Ground Floor	108.76	Sqm	201.50	Rs.21,914.00
10	6mm thick cement plaster (1:4) Over R.C.C. Surface including cost conveyance and royalty etc. complete.				
A	Ground Floor	116.72	Sqm	217.20	Rs.25,351.00
11	Supplying,fitting and fixing of M.S. Door and Window including all labours T&P etc. complete				
A	Ground Floor	921.25	Kg	152.33	Rs.140,332.00
12	Painting two coats with any approved paint including cost of primer,paints etc complete.				
A	Ground Floor	42.08	Sqm	182.00	Rs.7,659.00
13	20mm thick grading plaster (1:6) over rcc roof slab etc complete				
A	Ground Floor	74.83	Sqm	356.00	Rs.26,640.00
14	Finishing wall with Cement Based Wall Putty of approved make and finished smooth and even surface to receive painting including all cost				
A	Ground Floor	382.14	Sqm	83.90	Rs.32,061.00
15	Priming one coat with any approved primer including cost of primer including cost of primer,paints etc complete.				

