



**GOVERNMENT OF ODISHA
P.R. & D.W. DEPARTMENT**

**PANCHAYAT SAMITI,
RAIRANGPUR
MAYURBHANJ**

BID DOCUMENT

FOR 12 NOS OF CIVIL WORK

CONTENTS

Section	Items	Page No
Section-1	CHECK LIST TO BE FILLED UP AND SUBMITTED BY THE BIDDER	3
Section-2	Terms and Conditions	4-5
Section-3	DTCN	6-27
Section-4	Annexures	28-35
Section-5	BOQ for 12 Nos Works	

CHECK LIST TO BE FILLED UP AND SUBMITTED BY THE BIDDER

Name of the work :-

Name of the Contractor:-

House No./ Plot No.:-

AT :-

P.O:-

P.S:-

District:-


State:-

PIN:-

Sl. No	Particulars	Whether furnished	
		YES	NO
1	Cost of tender paper as mentioned in tender call notice shall be enclosed in original in shape of DD drawn in any nationalized bank.		
2	Earnest Money Deposit		
3	Contractor's Registration Certificate (License)		
4	Copy of valid GST clearance certificate		
5	Copy of PAN Card		
6	Certificate of Tools and Plants		
7	Complete filled in and duly certified Annexure-A, Annexure-B		
8	No Relationship Certificate in Annexure-C		
9	A declaration to the effect that there has been no conviction/imprisonment for an offence involving moral turpitude.		
10	Affidavit regarding authenticity of the credentials		
11	Attested Copies of Caste Certificate for ST/SC Contractor/ Affidavit claiming ST/SC		
12	Attested Copies of PH certificate for contractors claiming PH concession		
13	Signed Copy of DTCN and Price bid duly filled in & Signed by the bidder		
14	Bidder Contact Address Filling Mandatory.		

Signature of Contractor

[3]


Block Development Officer,
Raipur

Terms and condition


- 1 The Tender Paper can be downloaded from date 25.05.2026 to 06.06.2026 from the website <https://mayurbhanj.odisha.gov.in/>.
- 2 The sealed Tender Paper will be received on official working days from **07.00 AM to 01.00 PM** from date 25.05.2026 to 06.06.2026. The same should be submitted either through registered/ speed post addressing to the BDO, Rairangpur. The sealed envelope shall be super scribed as "Tender Paper". (Name of the Project). The undersigned will not be held responsible for any delay in the postal service.
- 3 The Tender Paper will be opened at **10.00 AM** on date 09.06.2026 in presence of the bidders or their authorized representatives and Block tender committee.
- 4 Earnest Money Deposit must be accompanied with the bid document of works Department Govt. of Odisha.
- 5 The following documents should be furnished along with the tender paper failing which the tender is liable for rejection.
 - a. Self Attested copy of the contractor valid registration certificate.
 - b. Attested copy of PAN CARD/ Labour License/GST clearance Certificate.
 - c. Demand Draft (Nonrefundable) amounting to Tender Paper Cost as Indicated in Bid Identification No. drawn in any nationalized Bank in favors of BDO Rairangpur.
 - d. Attested copy of caste certificate for SC/ST contractor desirous of availing preference.
 - e. Signed copy of DTCN and price bid duly filled in and signed by the tenderer.
 - f. An affidavit regarding authenticity of the credentials.
 - g. Name of the Project will be mentioned in cover of the Envelope.
 - h. Mailing address of registered office/site office of the bidders for future correspondence.
 - i. The EMD amount will be forfeited, if the Tenderer backs out from the offer of acceptance of Tender by the competent authority.
- 6 The Tender has to show all required original documents at the time of opening of the tender for verification.
- 7 An affidavit in support of the authority of document including No Relation Certificate and detail work programme should be attached with the Tender Paper.
- 8 Engineering contractors desired for EMD exemption must produce valid contractor registration certificate along with supporting affidavit.

Signature of Contractor


Block Development Officer,
Rairangpur

- If the rate quoted by the Tenderers is found to be same, Tender Committee will decide the Tender.
- 10 Excess bid amount quoted by the bidder, if any, in respect of any work shall not be accepted.
 - 11 The authority Reserves the rights to reject or cancel any or all the Tender without assigning any reason thereof.
 - 12 Omitted
 - 13 The tender is to be submitted in sealed envelope with all documents described and required as per the relevant clauses of the DTCN and Special Conditions if any. The envelope to be superscripted as the bid of the work as mentioned in column No.3 of the Tender Call notice.
 - 14 The Projects must be completed within the scheduled period of time, irrespective of receipt of allotment under the scheme.
 - 15 SC/ST Tenders can avail facilities as per Govt. circular.
 - 16 The bidder shall have to furnish an affidavit along with the bid regarding the authenticity of the bid document.
 - 17 Additional performance Security deposit shall be obtained from the bidder when the bid amount is less than estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price/rates than the estimated cost put to tender shall have to furnish the exact amount as specified in item no.5 of Bid Identification no. as Additional performance Security (APS) in shape of Demand Draft/ Term Deposit Receipt pledged in favor of Block Development Officer, Rairangpur within Seven days, otherwise the bid shall be cancelled and the security deposit shall be forfeited. Further, proceeding for blacklisting shall be initiated against bidder.
 - 18 All bids received will remain valid for a period of 90 days from the last date of receipt of bids and the validity of the bids can also be extended, if agreed to by the bidders with the Department.
 - 19 If the L-1 bidder does not turn up for agreement after finalization of tender, than she/he shall be debarred from participation in bidding for three years and action will be taken to blacklist the bidder. In that case L-2 bidder if fulfill, other required criteria would be called for drawing agreement for execution of work subject to the condition, that L-2 bidder negotiate at per with the rate quoted by the L-1 bidder otherwise tender will be Cancelled.
 - 20 The rates to be quoted by the contractor shall be excluding GST. The implementation of the GST rules by the Govt. of Odisha is to be accepted by the bidder at any point of time.
 - 21 Payment of work bill(S) will be made on receipt of allotment under the Scheme (Project allocation wise)

Signature of Contractor


Block Development Officer,
Rairangpur.

**GOVERNMENT OF ODISHA
DEPARTMENT OF PANCHYAT RAJ
INVITATION FOR BIDS (IFB) IDENTIFICATION NO.01 MBJ- RRP/ 2026-27
BLOCK DEVELOPMENT OFFICER, RAIRANGPUR
DETAILED TENDER CALL NOTICE**


1. The Block Development Officer, Rairangpur on behalf of Government of Orissa invites Percentage rate basis bids for execution of Civil works as detailed in the ANNEXURE 'A' from the Class of bidders registered with the State Government and bidders of equivalent Grade/Class registered for execution of Civil works on production of definite proof from the appropriate authority. The bidders may submit bids for any or all of the works annexed hereto.
2. Bid document consisting of plan, specification, the schedule of quantities and the set of items and conditions of contract and other necessary documents can be seen in the office of the undersigned during office hours every day except in Sundays and Public holidays till the last date of sale and receipt of bid documents.
3. Bids must be accompanied by original money receipt (Non-refundable) of bid document specified for the work as mentioned in the Col. No.6 of the ANNEXURE 'A' failing which the bid shall be liable for rejection. Bidders desirous to hire machinery or equipments from outside the State are required to furnish 2% of the amount put to bid as bid security.
4. The bid document can be downloaded from 25.05.2026 to 06.06.2026 and the bid documents shall be received from 07.00 AM to 01.00 PM from 25.05.2026 to 06.06.2026.
5. Bid information's can be obtained from website <https://mayurbhanj.odisha.gov.in/>.

Signature of Contractor


Block Development Officer,
Rairangpur.


6. The bid will be opened on 09.06.2026 at 10.00 AM at Conference Hall in the office of the Block Development Officer, Rairangpur in the presence of the bidders who wish to attend. If the office happens to be closed on the last date of receipt of the bids as specified, the bids will be received and opened on the next working day at the same time and same venue.
7. The value of the work put to bid is Rs. As per Col. No.5 of ANNEXURE – 'A'.
8. The bid document needs to be completed and submitted with copies of all the documents as required in the Invitation For Bids (IFB). Following is the summary of the copies of documents required to be submitted along with the completed bid document.
- (i) Contractor's Registration Certificate (License)
 - (ii) E.M.D. in the prescribed mode as required under clause 11 of DTCN.
 - (iii) GST Registration Certificate of the bidder along with GST clearance Certificate in Form 612 as required under clause 14 of DTCN.
 - (iv) Pan Card issued by the Income Tax Authority as required under clause 29 of DTCN.
 - (v) An affidavit regarding authenticity of the credentials as required under clause 25 of DTCN.
 - (vi) A declaration to the effect that there has been no conviction/imprisonment for an offence involving moral turpitude.
 - (vii) List of T & P/Vehicles/machineries in the prescribed proforma as required under clause 63 of DTCN.
 - (viii) Past performance of the Contractor in the prescribed proforma as required under clause 59 of DTCN.
 - (ix) No relationship certificate in the prescribed Proforma as required under clause 60 of DTCN.
 - (x) Compliance to qualifying criteria if any.
 - (xi) The mailing address of Registered Office/Site office of the bidder as required under clause 30 of DTCN.
 - (xii) Signed Copy of DTCN and Price bid duly filled is & Signed by the bidder.
 - (xiii) Attested Copies of Cast Certificate in case for ST/SC Contractor.
 - (xiv) Name of the Project & Sl. No. will be Superscribed in cover of the envelop.
9. The EMD will be forfeited if the bidder backs out from the offer before acceptance of bid by the competent authority as concurred in by Law Deptt. & Finance Deptt. In their UOR No. 848/L dt. 31.05.97 & UOR No. 202/WFD dt. 6.3.98 respectively. (Works Deptt. Memo No. 9101/dt.30.03.98)

Signature of Contractor


Block Development Officer,
Rairangpur.

- ed1
10. As the Orissa Sale Tax Act 1947 has since been repealed with effect from 1st April 2005 in the event of enactment of the Orissa Value Added Tax Act. 2004 and Rule 2005, caption 'Sales Tax' printed at various clause of DTCN stands modified as 'GST'. The bid shall not at the discretion of the competent authorities by considered unless accompanied by the true copies of GST Registration No. and valid GST clearance certificate in Form 612 issued by the Sales Tax Authorities and the original thereof to be produced if required at the time of opening of the bid. The bidder registered in other State Government is required to produce non-assessment certificate obtained from the Sales Tax Commissioner Government of Orissa at the time of submission of bid document. The rates quoted by the bidder shall be deemed to be inclusive of GST of all the materials that he will have to procure for performance of the contract. Deduction of GST at source @ 18% from the gross amount payable to the bidder shall be made and credited to the Government in terms of statutory provision U/S 54 of the Orissa GST Act. 2004.
 11. The earnest money will be retained in case of successful bid and will be dealt with as per the terms and conditions of the O.P.W.D. Code and will not carry any interest. The earnest money of the unsuccessful bidder will be refunded on application after the tender is finally accepted and agreement concluded.
 12. The bidder whose bid is selected for acceptance and who has no fixed deposit with the Government of Orissa, shall within a period of seven days upon intimation given to him of acceptance of his bid make an initial security deposit in the form of NSC/ Post Office Time Deposit/Post Office Savings Bank Account/ Kisan Vikas Patra / Deposit receipt of Scheduled Bank and in no other form as earnest money shall be 1% of the value of the bid amount and sign agreement in the P.W.D. form No. F2 (Schedule XLV No.61) for the fulfillment of the contract in the office of the Block Development Officer, Rairangpur. The security deposit together with the earnest money and the amount withheld according to the provision of F2 agreement shall be retained as security for the due fulfillment of this contract. Failure to enter into the required agreement and to make the security deposit as above shall entail forfeiture of the earnest money. No bid shall be finally accepted until the required amount of security money is deposit. The written agreement to be entered into between the bidder and the Government shall be the foundation of the rights of both the bidder and the Government and the contract shall be deemed to be incomplete until the agreement has first been signed by the bidder and then by the proper officer authorized to enter into the contract on behalf of the Government. The security deposit will be refunded after one year from the date of completion of the work and payment of the final bill. This will not carry any interest.
 13. Bid must be submitted in sealed covers. Bid documents received after due date and time will not be entertained. No bidder will be permitted to furnish his bid in his own manuscript.
 14. The work is to be completed in all respect within the stipulated date which is mention in DTCN.
 15. All bids received with remain value for a period of one's month from the date of receipt of bids or till the date of drawl of Agreement whichever is earlier and validity of bids can also be extended if agreed by the bidder and the Department.
 16. The date of issue of the notice to the bidder to attend Block office for signing the agreement shall be treated as the date of commencement of work, unless otherwise specifically mentioned. The bidder whose bid is accepted must submit a programme of work immediately after issue of work order for approval by the Engineer-in-charge.
 17. The bidder shall carefully study the tentative drawing and specifications applicable to the contract and all documents, which form part of the agreement to be entered into by the accepted bid and detailed standard and specifications for Orissa and other relevant specifications and drawings, which are available for sale. Complaint at a future date that and specifications have not been seen by the bidder cannot be entertained.

Signature of Contractor


Block Development Officer,
Rairangpur.

18. Every bidder is expected before quoting his rates to inspect the site of the proposed work. He should also inspect the quarries and approach road to quarries and locality of the work and satisfy himself about the quality and availability of materials including the medical aids, labour and foodstuff etc. In every case the materials must comply with the relevant specifications.

The bidder will be deemed to have satisfied himself that the rates quoted by him in the bid will be adequate to complete the work according to the specifications and conditions attached to and that he has taken into account all conditions, difficulties that may be encountered during its progress and to have quoted labour rates and materials, entry tax and other duties, leads, lifts, delfts, loading and unloading and freight for materials and all other incident charges necessary for the completion of the work to the entire satisfaction of the Engineer-in-charge of the work and his authorized subordinates. In the course of awarding a work, the Department may desire the analysis of the rate arrived for against any item(s) of work.

Complaints at future date that the availability of materials, labour or any other factor have been misjudged cannot be entertained. It should be understood clearly that no claim whatsoever will be entertained afterwards on the plea of non-availability of proper quantity and quality of materials, including foodstuffs or fol any other.

19. The bidder shall bear in full various incidentals, sundries and contingencies necessitated by the work within the following or similar category.

- a) Rent, royalties and other charges of materials octroi duty, entry tax, all other taxes payable under various Acts & Rules including GST, ferry tolls, conveyance charges and other cost on account of land buildings including temporary building and temporary electric connection to work site as well as construction of coffer dam, construction of service road, haul road, diversion and its maintenance till completion of work required by the bidder for collection of materials, storage housing of staff or other purpose of the work.
- b) Labour camps or huts necessary to a suitable scale including conservancy and sanitation arrangements therein to the satisfaction of the local health authorities should be arranged by the bidder.
- c) Suitable water supply including pipe water supply wherever available should be provided for the staff and labour as well as for the work.
- d) Fees and duties levied by the municipal/ canal or water supply authorities.
- e) Suitable equipment and wearing apparatus for the labour engaged in risky operations and medical aid to the labourer engaged for the work.
- f) Suitable fencing, barriers, signals including paraffin and electric signals wherever necessary at work and approaches in order to protect public and employees from accident
- g) Compensation including cost of any suit for injury to persons or property due to neglect of any major precautions also become payable due to operation of the Workman's Compensation Act.
- h) The bidder has to arrange adequate lighting arrangement for the work wherever necessary at his own cost.

Signature of Contractor


Block Development Officer,
Rairangpur.

20. Additional Performance Security (APS) shall be obtained from the successful bidder in case the quoted bid price is below the estimated cost put to tender, in accordance with the incremental APS system notified by the Government of Odisha, Works Department vide Office Memorandum No.173/W dated 03.01.2026 and clarification issued vide OM No.632/W.


The APS shall be calculated and deposited as under:

Amount of Additional Performance Security		
SI No	Range of Difference between the estimated cost put to tender and Bid amount	Additional performance security to be deposited by the successful bidder
1	Below 0% but not below 10%	No Additional Performance Security
2	Below 10% but not below 20%	The Additional Performance Security shall be incremented at the rate of 0.1% of the bid price for every percentage of bid price below 10%, starting at 11%, and shall be applied on the bid price.
3	20% or more below	The Additional Performance Security shall be 1% of the bid price plus an increment of 0.2% of the bid price for every percentage of bid price below 20%, and shall be applied on the bid price.

- The Additional Performance Security percentage shall be rounded off to the next lower percentage if the decimal point is below 0.5%, and to the next higher percentage if the decimal point is 0.5% or more.
- The Additional Performance Security shall be treated as part of the Performance Security.
- Justification for abnormally low bids shall be scrutinized by the Departmental Technical Committee and recommended to the competent authority of the Administrative Department for the approval of the Additional Performance Security (APS). An abnormally low bid is one in which the Bid price, in combination with other elements of the Bid, appears so low that it raises material concerns as to the capability of the Bidder to perform the contract at the offered price. Procuring Entity may, in such cases, seek written clarifications from the Bidder, including detailed price analyses of its Bid price in relation to scope, schedule, resource mobilization, allocation of risks and responsibilities, and any other requirements of the bid document. If, after evaluating the price analyses, the procuring entity determines that the Bidder has substantially failed to demonstrate its capability to deliver the contract at the offered price, the Procuring Entity may reject the Bid/ Proposal. However, it would not be advisable to fix a normative percentage below the estimated cost, which would automatically be considered as an abnormally low bid.
- The APS shall be furnished in the shape of Demand Draft / Term Deposit Receipt pledged in favour of the Block Development Officer, Naugaon from any Nationalized / Scheduled Bank in India, within seven (7) days from the date of issue of Letter of Acceptance (LoA), failing which the bid shall be cancelled and the EMD shall be forfeited. Further action including blacklisting shall be initiated as per OPWD Code provisions.

21. The bidders shall have to sign on each page of tender schedule, DTCN and the credentials submitted by him. In addition bidders shall have to submit an affidavit along with the bid regarding authentication of bid documents, credentials including security deposits/additional performance security deposits. The bidder shall not be allowed to engage power of Attorney holder for the purpose.

Signature of Contractor


Block Development Officer,
Rairangpur.

[10]

22. In event of item rate bid each bidder must quote a definite rate for each items of work for subsequent inclusion in the contract. Bids containing indefinite terms such as estimated rates or schedule of rates or rates on percentage basis will not be considered. The bidder may at his option quote reasonable rate for each item of work carefully so that the rate for one item should not be unworkably low and for other too high.

23. All rates should be for finished items of works unless otherwise specifically mentioned in the tender schedule.

24. In case of Item rate bids, the rate should be written both in words and figures and in decimal coinage and in case of discrepancy in rates between words & figures the rates written in words will prevail. The bidders may also show the total of each item and the grand total of the whole bid. In case of discrepancy in the rates quoted against each item of work in figure and total of each item, the lesser amount shall be treated as valid.

In case of Percentage rate contracts the schedule of quantities shall mention estimated rate of such item and amount thereto. The bidder has to mention percentage excess or less over the estimated cost (in figures as well as words) in the prescribed format appended to the bid document. The bidders participated in the bid for more than one work may offer conditional rebate. Rebate offer submitted in separate sealed envelope shall be opened, declared and recorded first. The rebate so offered, shall be considered after opening of all packages called in the same bid invitation notice.

In case of percentage rate bids, only percentage quoted shall be considered. Percentage quoted by the bidders shall be accurately filled in figures and words, so there is no discrepancy. If any discrepancy is found in the percentage quoted in words and figures, then the percentage quoted by the bidder in words shall be taken as correct. If any discrepancy is found in the percentage quoted in percentage excess/less and total rate quoted by the bidder then percentage will be taken as correct. The percentage quoted in the bid without mentioning excess or less and not supported with the corresponding amount will be treated as excess. The bidder will write percentage excess or less up to one decimal point only. If he writes the percentage excess or less upto two or more decimal points, the first decimal point shall only be considered without rounding off. Where the bidder has omitted to quote the rates either in figures and words, the Officer opening the bid should record the permission.

- If the bidder is not willing to accept the amount so fixed in the above manner and declines to execute the work the EMD of the bidder shall be forfeited to Government. Bills for percentage rate bids shall be prepared at the estimated rates for individual items only and the percentage excess or less shall be added or subtracted from the gross amount of the bill.
- The bid should be written legible and free from erasures overwriting or correction of figures and words and all overwriting should be neatly scored out and rewritten and corrections whenever unavoidable should be done by writing over the dated initial of the bidder.

25. In accordance with Section 194C of The Income Tax Act 1961, 2% (two percent) of the gross amount of the bill followed by Surcharge and Education Cess (as admissible) shall be deducted towards Income Tax from the bills payable to the bidder. The bidder shall have to furnish true copy of PAN Card issued in accordance with the provisions of The Income Tax Act 1961 along with the bid.


26. The bidder shall have to furnish the complete postal address of his address of his Registered Office as well as Site Office for making all future correspondences. Any notice or instructions to be given to te bidder under the terms of the D.T.C.N/ Agreement shall be deemed to have been served upon him if and only if dispatched by Registered Post in the address of his registered office / site office or in the mailing address last provided by him.

Signature of Contractor


Block Development Officer,
Rairangpur.


27. Labour Cess as admissible shall be deducted from the gross amount of the bill payable to the bidder.
28. The bid containing extraneous conditions not covered by the invitation notice are liable for rejection and quotations should be strictly in accordance with the bid invitation notice. Any change in the wording will not be accepted.
29. Conditional bids will not be taken into consideration.
30. On no account, whole or any part of the contract work shall be sublet / off loaded to surrogated executants or transfer be made by execution of a deed of Power of Attorney (hereinafter called as 'subletting') without prior written approval of the competent of the Department. In such an event the arrangement may be rescinded. The bid accepting authority shall keep the following points in view in the event of grant of such permission for subletting. Wherever such approval is granted, the bidder shall not be relieved of any obligation or duty or responsibility, which he undertakes under the Agreement.
- (i) Subletting shall be permitted only in exceptional cases and for recorded reasons as to why the Contractor himself can not directly run the Contract.
- (ii) In all cess, Sublette shall be a Contractor of the same or higher capacity or class as the original Contractor.
- (iii) Sanctioning authority shall see he qualifying criteria of the bid including the filled in Proforma annexed vide ANNEXURE'S of DTCN, so as to assess the capability of the Sublette.
- (iv) Sanctioning authority shall also see the terms and conditions of the agreement between the Contractor and the Sublette in order to satisfy himself that the Contractor is not subletting the work for carrying a middleman's profit.
- (v) It shall be observed at the time of subletting that the Government will not be put to any loss on account of substandard execution due to compromise in the quality of work and materials.
31. Letters etc. found in the tender box raising and lowering the rates or dealing with any point in connection with the item rate bid will not be considered.
32. Schedule of Quantity accompanies the bid invitation notice: It shall be definitely understood that the Government do not accept any responsibility for the 'correctness and completeness' of this schedule and this schedule is liable for alternations or omissions, deductions or addition as set forth in the conditions of contract and such omissions, deductions, additions or alternations shall in no way invalidate / validate the contract and no extra monetary compensation will be entertained.
33. The authority reserves the right to make such increase or decrease in the quantity of items of works mentioned in the schedule attached to the bid invitation notice as may be considered necessary for the satisfactory completion of the contract work. All such increase or decrease shall in no way invalidate / vitiate the contract rates. The bidder shall not be entitles for any compensation on this account except for grant of extension of time wherever considered necessary.
34. Items of work not covered by the bid invitation notice shall be paid at the prevailing schedule of rates based on actual analysis approved by the competent authorities on execution of Supplementary Agreement.
35. During execution of the work, there is every likelihood of such items of work, which do not find place in the current schedule of rates or in respect of such items, which are given in the schedule of items for which the bidder has not quoted his rates. The bidder will have to carry out these items of work. Rates of such items of work which do not find place in the current schedule of rates referred to above shall be decided by the AEO Tech. of the DRDA, Mayurbhanj and the decision of the AEO Tech., shall be conclusive and binding upon the bidder. The payment on such items of execution shall be made on drawl of Supplementary Agreement.

Signature of Contractor


Block Development Officer,
Rairangpur.

36. The quantities in respect of the items for which the quoted rates are more than 212% of the estimated rates are not allowed to be varied by more than five percent. In case, it seems to exceed the limit prior approval of the competent authority should be obtained in accordance with Para 6.3.15 of OPWD Code (Vol.I)
37. It should be understood clearly that no claim whatsoever will be entertained in regard to extra items of work or extra quantity of any item besides, estimated amount, unless written order is obtained from the Engineer-in-charge and rates settled and supplementary agreement drawn before the extra item(s) of work are taken up.
38. The work may be splitted up and distributed among several Agencies if considered necessary on the exigency of the circumstances of the work and the bidder is not entitled to any compensation on this account.
39. Under Section 12 of Contract Labour (Regulation and Abolition) Act. 1970 the bidder who undertakes execution of work through labour, should produce valid license from licensing authority of Labour Department (labour license) before drawl of agreement.
40. In every case in which by virtue of the provisions of Section 12, sub-section (I) of the Workman's Compensation Act, 1923, Government is obliged to pay compensations to a workman employed by the contractor in execution of the works, Government will recover from the contractor the amount of compensation so paid and without prejudice to the rights of Government under Section (I) sub-section (2) of the said Act, Government shall be at liberty to recover the amount or any part thereof by deducting it from the security deposit or from any sum due by Government to the contractor whether under this contract or otherwise Government may not be bound to contest any claim made against them under Section 12, sub-section (I) of the said Act except on the written request of the contractor and upon his giving to Government full security for all cases for which Government might before liable in consequence contesting such claim.
41. Bidders are required to abide by the fair wages clauses as introduced by Government of Orissa and will not pay less than the Fair Wages fixed by Government to the labourers engaged by him for the work. In case of any complaint by the labourer about the non payment of his wages as per the Prevailing Minimum Wages Act, the B.D.O. shall have the right to investigate and if the bidder is found to be default, the Block Development Officer may recover such amount due from the bidder and pay such amount to the labour directly under intimation to the local Labour Office of the Government. The decision of the Block Development Officer is final and binding up on the bidder. An undertaking to this effect is annexed herewith vide ANNEXURE 'B'.
42. The bidder will have to submit the Block Development Officer, Rairangpur monthly return of labour both skilled and unskilled employed by him in the work. The bidder should keep himself in touch with the Engineer in charge for smooth execution of the work and arrange adequate labour depending on the workload and working space available. No claim for detention of labour on any account will be entertained.
43. Any damaged cause to the work due to 'any cause' whatsoever during excecution, the bidder will make good until it is handed over to the Department in complete shape. Any cause shall mean and include' National Calamities of all kinds.
44. The bidder shall have to abide by the C.P.W.D. Safety Code Rules introduced by the Govt. of India Ministry of Works, Housing and Supply vide order no. 44150 dt. 25.1.1957.
45. All preliminary works such as GSTs, mixing platform etc. are to be done by the bidder at his own cost. No payment will be made for benchmarks, level pillars, profiles, benching and leveling the ground wherever required. The rates to be quoted should be for finished item of work inclusive of carriage of all materials and incidental items of works.

Signature of Contractor


Block Development Officer,
Rairangpur.

46. After the work is finished all surplus materials & debris should be removed 100m. clear away from the site of the work. Preliminary work such as GSTs, mixing platforms etc, should be dismantled and all materials removed from the site and premises be left neat and clean and this should be inclusive of the rates.
47. In view of the addendum to the conditions of contract, vide Works Department Circular No. 24716 Dt. 24.12.2005 the existing / relevant provisions incorporated in this DTCN/Original standard F2 Agreement stands modified to the extent as detailed herein below. This addendum shall be conclusive and binding upon the bidder and shall form part of the Agreement.

Time Control.

A. Progress of Work and Re-scheduling Programme.

- i) The Block Development Officer shall issue the letter of acceptance to the successful bidder. The issue of the letter of acceptance shall be treated as closure of the bid process and commencement of the contract.
- ii) Within 15 days of issue of the letter of acceptance, the bidder shall submit to the Engineer-in-charge for approval of a programme commensurate to clause no. (ii) showing the general methods, arrangements and timing for all the activities in the work along with monthly cash flow forecast.
- iii) To ensure good progress during the execution of the work the bidders shall be bound in all cases in which the time allowed for any work exceeds one month to complete, 1/4 the whole time allowed under the contract has elapsed, 1/2th of the whole of the work before 1/2 of the whole time allowed under the contract has elapsed, 3/4th of the whole of the work before 3/4th of the whole time allowed under the contract has elapsed.
- iv) If at any time it should appear to the Engineer-in-charge that the actual progress of the work does not confirm to the programme to which consent has been given, the bidder shall produce, at the request of the Engineer-in-charge, a revised programme showing the modifications to such programme necessary to ensure completion of the work within the time prescribed for completion. If the bidder does not submit an update programme within this period, the Engineer-in-charge may withhold the amount of 1% of the contract value from the next payment certificate and continue to withhold this amount until the next payment after the date on which the over due programme has been submitted. An update or the programme shall be a programme showing the actual progress achieved on each activity and the effect of the progress achieved on the timing of the remaining work including any changes to the sequence of the activities.
- v) The Engineer-in-charge's approval of the programme shall not alter the bidder's obligations. The bidders may revise the programme and submit it to the Engineer-in-charge again at any time. A revised programme is to show the effect of Variations and Compensation Events.

B. Extension of the Completion Date.

The time allowed for execution of the work as specified in the contract date shall be the essence of the Contract. The execution of the work shall commence from the 15th day or such time period as mentioned in Letter of Award after the date on which the Engineer-in-charge issues written order to commence the work or from the date of handing over of the site whichever is latter. If the bidder commits default in commencing the execution of the work as aforesaid, Government shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the Earnest Money Deposit and Performance Guarantee/Security Deposit absolutely.

Signature of Contractor


Block Development Officer,
Rairangpur.

As soon as possible after the contract is concluded the bidder shall submit a Time and Progress Chart for each milestone and get it approved by the Department. The chart shall be prepared in direct relation to the time stated in the Contract documents for completion of items of the work. It shall indicate the forecast of the dates of commencement and completion of various trades of section of the work and may be amended as necessary by agreement between the Engineer-in-charge and bidder within the limitations of time imposed in the contract document, and further to ensure good progress during the execution of the work, the bidder shall in all cases in which the time allowed for any work, exceeds one month (save for special jobs for which a separate programme has been agreed upon) complete the work as per milestone given in contract data.

In case of delay occurred due to any of the reasons mentioned below, the bidder shall immediately give notice thereof in writing to the Engineer-in-charge but shall nevertheless use constantly his best endeavors to prevent or make good the delay and shall do all that may be reasonably required to the satisfaction of the Engineer-in-charge to proceed with the work.


- (i) Force majeure, or
- (ii) Abnormally bad weather, or
- (iii) Serious loss or damage by fire, or
- (iv) Civil commotion, local commotion of workmen, strike or lockout, affecting any of the trades employed on the work, or
- (v) Delay on the part of other contractors or tradesmen engaged by Engineer-in-charge in executing work not forming part of the Contract.
- (vi) In case a variation is issued which makes it impossible for completion to be achieved by the intended completion date without the bidder taking steps to accelerate the remaining work and which would cause the bidder to incur additional cost, or
- (vii) Any other cause, which in the absolute discretion of the authority mentioned, in Contract date is beyond the bidder's control.
Request for re-schedule and extension of time, to be eligible for consideration shall be made by the bidder in writing within fourteen days of the happening of the event causing delay. The bidder may also, if practicable, indicate in such a request the period for which extension is desired.
- (viii) In any such case a fair and reasonable extension of time for completion of work may be given. Such extension shall be communicated to the bidder by the Engineer-in-charge in writing, within 3 (three) months of the date of receipt of such request. Non-application by the bidder for extension of time shall not be a bar for giving fair and reasonable extension by the Engineer-in-charge and this shall be binding on the bidder.

C. Compensation for Delay.

If the bidder fails to maintain the required progress in terms of Clause "A" (Time Control) or to complete the work and clear the site on or before the contract or extended date of completion, he shall, without prejudice to any other right or remedy available under the law to the Government on account of such breach, pay as agreed compensation the amount calculated at the rates stipulated below as the AEO Tech. (whose decision in writing shall be final and binding) may decide on the amount of tendered value of the work for every completed day/month (as applicable) that remains below that specific in Clause "A" (Time Control) or that the work remains incomplete.

This will also apply group of items for which a separate period of completion has been specified. Compensation @ 1.12% per month of delay of work to be computed on per Day basis.

Signature of Contractor


Block Development Officer,
Rairangpur.

Provided always that the total amount of compensation for delay to be paid under this condition shall not exceed 10% of the Bid Value of work or to the Bid Value of the item or group of items of work for which a separate period of completion is originally given. The amount of compensation may be adjusted or set-off against any sum payable to the bidder under this or any other contract with the Government in case, the bidder does not achieve a particular milestone mentioned in contract data, or the rescheduled milestone(s) in terms of Clause "E" (Management Meeting) the amount shown against that milestones shall be withheld, to be adjusted against the compensation levied at the final grant of extension of time. Withholding of this amount on failure to achieve a milestone shall be automatic without any notice to the bidder. However, if the bidder catches up with the progress of work on the subsequent milestone(s), the withheld amount shall be released. In case the bidder fails to make up for the delay in subsequent milestone(s), amount mentioned against each milestone missed subsequently also shall be withheld. However, no interest whatsoever shall be payable on such withheld amount.

D. Management Meetings

Either the Engineer or the bidder may require the other to attend a management meeting. The business of a management shall be to review the plans for remaining work and to deal with matters raised in accordance with the early warning procedure.

The Engineer shall record the business of management meetings and is to provide copies of his record to those attending the meeting and to the Employer. The responsibility of the parties for actions to be taken is to be decided by the Engineer either at the management meeting or after the management meeting and should be stated in writing to all who attended the meeting.

48. In case of delay in acquisition of land/handing over possession of work site no compensation will be admissible but extension of time will be allowed if applied in the proper format.


49. If a bidder removes any Govt. material or stores supplied to him from the site of the work in contravention of the provision of this clause with a view to dispose of the same dishonestly, he shall be in addition to any other liability civil or criminal arising out of the contract be liable to pay penalty equivalent to five time of the price of the materials or stock. The penalty so imposed shall be recoverable at any time from the sum that may be due then or at any time thereafter become due to the bidder or from his security deposit or the proceeds of sale thereof. The bidder will be responsible for the misuse, loss, and damage due to any reason whatsoever on any materials of the Department supplied to him for the execution of the work. In case of loss damage or misuse of the Departmental materials issued to him recovery at the rate at that time (i.e. market rate or the issue rate of the Department which ever will be more) will be deducted from the bills or his other dues.

50. Over and above these conditions including the technical specifications the terms, condition, rules and regulation and specifications laid down in Orissa Detail Standard & Specification Code are also binding upon the bidder.

51. DELETED

The onus of establishing a credential solely lies with the bidder. The Department shall in no way be held liable for creating credentials Suo motto from the official records but to examine the authenticity of the credentials furnished by the bidder along with the bid.

Signature of Contractor


Block Development Officer,
Rairangpur.

52. No Relationship Certificate.

The bidder shall have to furnish a certificate along with the bid to the effect that he is not related to any officer in the rank of an Asst. Engineer and above in the State P.W.D. or Asst. Secy. And above in the water Resources Department. If the fact subsequently provides to be false the contract will be rescinded. The earnest money and the total security will be forfeited and he shall be liable to make good the loss or damage resulting from such cancellation. The proforma for no relationship certificate is enclosed herewith vide ANNEXURE 'C'.

53. The bidder shall sign as a token of final acceptance of the plans, sections and agreements for the work prior to take up the work for execution.

54. The bidder has to supply necessary labor and materials for the purpose of alignment laying whenever required at his own cost.

55. The bidder should arrange necessary tools and plants, vehicles, machineries such as pump, road rollers etc. required for the efficient execution of work at his own cost. The running charges of such plant and cost of consumables and conveyance are to be borne by the bidder.

56. In the event of delay in supply of departmental materials and supply of design reasonable extension of time shall only be granted on the application of the bidder. No claim for monetary compensation will be entertained under any circumstances.

57. Under no circumstances, interest shall be chargeable for the dues or any additional dues, if any payable for the work.

58. Protection against flood.

In case of flash and untimely floods in the river during the period of execution resulting in overtopping of coffer dam and flooding of the work area, the bidder shall make his own arrangement at his cost to shift the machineries, equipment's, materials labour and departmental machineries if hired by the bidder to a safe place. The work shall have to be resumed after receding of floods and necessary strengthening of cofferdam and the bidder at his cost will do dewatering. The Department may consider extension of time for the completion of the work if the discontinuance of the work is beyond all reasonable attempts of the bidder to such eventualities.

The debris, sand and other materials, accumulated in the working area during flash floods or regular floods in the monsoon shall be removed by the bidder as required for continuing the work at his own cost. By any chance, if any excavated portion that could not be filled with concert by the bidder, gets filled up during the monsoon period with earth such removal will not be paid further. The bidder will have to re-excavate the same at his own cost.

It shall be distinctly understood that it is entirely the responsibility of the bidder to make such arrangement as may be required from time to time to protect the men, machinery materials and the work under progress and the work for which the measurements were recorded and payment made, against damages either during working season or during the flood season. The Department accepts no liability, what so ever for any damage or loss of men, materials and the work if such hindrance is caused to the progress of work.

The bidder should provide at his own cost adequate protective measures to the completed works at the end of working season or working in progress flood during monsoon till completion and handing over of the entire work.

Signature of Contractor



Block Development Officer,
Rairangpur.

59. During Excavation of out-off trench, shoring, shuttering cost and carnage of materials including all taxes to be borne by the bidder. Only the designed sectional quantity will be paid. Dewatering from the foundation trench including hire and running charges of pump will be borne by the bidder.

60. Earth Work:


- a) The earth work quantity will be assessed from cross section taken at suitable intervals as decided by the Engineering-in-charge. Initial levels will be taken with reference to the benchmark, which should be kept at site till finalization of the contract. Both the parties to the contract should sign the initial cross sections before starting the work. Final level is to be taken and recorded in level book after completion of the work in all respect and the bidder is to sign the final level recorded by the department in token of acceptance of final measurements. The plotting of final levels should also include initial level, designed level & executed level in three distinct indelible ink. At the time of recording of such level by the Department, the bidder shall have to deploy his qualified Engineers, so as to assist him to witness the levels.
- b) Payment for earth in banking by section measurement, will be made by deduction 12.5% (twelve and half) and 5% (five percent) towards settlement if measurement is taken before monsoon and after one monsoon respectively.
- c) If final measurement of earth is taken after two successive rainy seasons and after due settlement of earth work, minimum settlement allowance will be deducted on actual observation by the Engineer-in-charge.
- d) Borrowing of approved type of earth and disposal of cutting earth are at the cost and risk of the bidder. The Department is in no way liable for any damages caused to any individual(s) nor shall any extra payment be made to the bidder.
- e) Earth work beyond the required design section will not be paid.
- f) Earth available from cutting sections should be utilized in filling sections.
- g) The earthwork includes all leads, lifts & delfts including conveyance by all means i.e. by manual, mechanical or both.
- h) Regular reliable borrow pits witness are essential for maintenance for which the bidder shall be responsible. If he fails to make or maintain borrow pits and witness in the reliable manner to the satisfaction of the Engineer-in-charge, the later may at his option re-ensure the cubic contents of earth on embankment and deduct from the bill of the bidder such percentage which may be judged towards shrinkage settlements and also be in such adjustment as he thinks fit considering all leads and payment be made in the event of entertained by the Department on the curtailment of earth work extra leads and lifts.

61. Specification for Breach Closing works in River Embankments:

Before breach closing, the scour pocket filled with water should be dewatered and dried. The seat of the embankment should be ploughed 8" deep before earth is put in for which no extra payment will be made.

62. a) The rates quoted by the contractor shall be deemed to be exclusive of GST on all the materials that he will have to purchase for performance of this contract.

Signature of Contractor


Block Development Officer,
Rairangpur.

- b) The rates quoted by the contractor in the tender for works shall exclude GST that may be levied on turnover on works contract according to the Laws and Regulations as applicable from time to time & as amended from time to time of GST Act-2017.
- c) GST on works contract will be deducted at applicable rate from the bill and credited to Govt. account.
- d) 1 % (One percent) of the gross amount of the bill will be deducted from the contractors bill towards **labour Cess** as per Odisha building and other construction workers (RE & CS) rules 2002 and Amendment during 2008 and as amended by Govt. from time to time.
- e) Income Tax at applicable rate shall be deducted at source.
63. The contractors are required to pay the Royalty as fixed by Govt. & amended from time to time, on minor minerals, otherwise royalty on such materials will be deducted and credited to Govt. Account.

64. Cement Concrete :

Concrete work will conform to IS-456-2000. Concrete shall consist of :

General :

Concrete shall be composed of cement, sand, coarse aggregate, water admixture (if any) as specified and well mixed in concrete mixture by weight and brought to proper consistency. In case the quantity of concrete involved in work is very small, the Engineer-in-charge may allow volumetric proportioning of concrete mix for the restricted quantity.

Mixing :

Concrete shall be mixed in a mechanical mixer with a mixing time not less than 2½ minutes and shall be as dense as possible. Mixing shall be continued until there is a uniform mixing of the materials and the concrete is uniform in colour and consistency. The time of mixing shall conform to table 1 of IS 457-1957.

Materials :

a) Sand (Fine Aggregate)

Sand to be used in the work shall be natural and free from organic impurities, the maximum size being limit to 4.75 mm. Fineness modules shall be minimum of 2.2 and specific gravity not less than 2.5, bulkgage of wet sand shall be a maximum of 20%.

b) Coarse Aggregate:

Maximum size of coarse aggregate shall be 40mm and downgraded to have well graded aggregate. Specific gravity shall not be less than 2.5 in order to have well graded aggregate it shall conform to the following table.

TABLE

I.S. Sieve	% Passing for graded aggregates of nominal size			
	40mm	20mm	16mm	12.5mm
40mm	95-100	100	-	-
20mm	30-70	95-100	100	-
16mm	-	90-100	100	-
12.5mm -	-	-	-	90-100
10mm	10-35	25-55	30-70	40-85
4.75 mm	0-5	0-10	0-10	0-10
2.36 mm				

Signature of Contractor


Block Development Officer,
Rairangpur.

c) **Cement**

Ordinary Portland cement shall be used in all cases except in structure in saline locations where Portland slag cement shall be used. Other essential requirements to be fulfilled by chemical analysis.

Quality control organization shall be referred to conduct periodic physical/chemical tests of cements to ensure the quality and such testing charges shall be borne by the bidder.

Table - A

Sl. No.	Grade of Concrete	Cement level required with coarse aggregate of maximum size (MSA) 40mm & downgraded	20mm & down graded
1.	M-10	207 Kg./M ₃	221 Kg./M ₃
2.	M-15	259 Kg./M ₃	228 Kg./M ₃
3.	M-20	329 Kg./M ₃	366 Kg./M ₃

Actual cement level required for the aggregates to be used shall be determined by laboratory test. The mix shall be designed to produce the grade of concrete having to required workability and characteristic strength as stipulated in the following table.

Table - B

Sl. No.	Grade of Concrete	Compressive test strength in N/mm ² on 150 mm cube conducted in accordance with IS 456-2000 Minimum at 7 days	Minimum 28 days
1.	M-10	7	10
2.	M-15	10	15
3.	M-20	13.5	20

N.B.:- In case of actual cement use being less than the cement level specified in Table-A, the Department shall deduct the cost of cement from the bill of the bidder at the prevailing predetermined price of cement for short consumption of cement. In case, of actual cement used being more than that specified in Table-A, the bidder shall be paid for extra cement used at the predetermined price of cement. Design mix and actual cement level required shall be communicated to the bidder from the to time in writing by the Engineer-in-charge.

65. All reinforcement cement concrete work shall conform to Orissa Detailed Standard Specification, I.R.C. and I.S.I. Code and should proof 1:2:4 with 6 mm to 18 mm size hard broken granite chips (18mm size not exceeding to 212%)

66. Shuttering and centering shall be with seasoned non-sal wood, the inside of which should be lined with suitable sheeting and be made leak-proof and watertight or alternative steel shuttering and centering shall be preferred.

67. Cement concrete in roof slab beams and wherever prescribed by the Engineer-in-charge will be machine mixed and the bidder should arrange his own concrete mixture, vibrator, pumps etc. for which no extra payment shall be made.

68. All the quantities mentioned in the schedule are combined for ground and multi storied floors in case of multi-storied building, the rates should be through for the same

Signature of Contractor


Block Development Officer,
Rairangpur.

69. The exposed surface of all the reinforced cement concrete works should be made smooth and no extra charges for plastering if required to any R.C.C. structures like columns, chajas, deck slabs, walls or R.C.C. works will be paid for the purpose.
70. The depth of foundation indicated in the drawing are provisional but these may be altered if considered necessary in the light of the nature of soil assessed by boring which must be taken in advance of the actual execution to the instructions.
71. The thickness of cement concrete in top plugging should be as per the department drawing.
72. Concrete of strength below 812% of the required strength (as determined by actual test) shall not be accepted.
73. Materials for lining work should be used in the work only after obtaining approval of the Engineer-in-charge.
74. Cement shall be used by bags and weight of a bag of cement being taken as 50kg or weight of one cubic meter of cement be taken as 14.42 quintals.
75. For concreting the bottom plugs of well under water the method of pouring concrete should be either with baskets or boxes or bags as directed by the Engineer-in-charge. 10% extra cement should be used for underwater concreting without any extra cost to the Department.
- 76. Curing :**
Curing of all cement works will be done by the bidder as per the instruction of the Engineer in-charge, at his own cost.
77. The Department shall have the right to inspect the scaffolding and centering made for the work and reject partly or fully such structures if found defective.
78. In the event of any work tendered for under 'Food for work Programme' the payment shall be made in terms of CASH AND / OR GRAIN in accordance with Deptt. Of Water Resources Circular No. F.C.III-3/2001 / 22859 Dt. 19.6.2001 read with DOWR resolution No. F.C. III-59-2003/27799 dt.11.8.03 and further modifications if any. In the works covered under Food For Work Programme the bidder shall have to maintain Muster Rolls in support of Payment of Wages in shape of food grain to the labourers engaged in the work. After issue of food grains by the Department will be the bidders' exclusive responsibility for transportation, safe custody and up-keepment till the food grains are provided to the labourers engaged in the bonafide Government work against proper acknowledgement in Muster Rolls. The bidder shall have to bear all such incidental charges such as transportation, storage, handling etc. and cost of empty gunny bags @ Rs.4.00 /- per bag, the rates quoted for the work are to be inclusive of all such charges. A Proforma of undertaking is appended to the Agreement vide ANNEXURE 'B'.
79. The length and section of reinforcement after it is put in position as per design will be measured for the purpose of payment including weight of binding wire.
80. Concrete should be vibrated with skin vibrator and pan vibrator. If available, the Department will supply these vibrators on payment of usual hire charges.
81. It must definitely understood that the Department shall not accept any responsibility for the correctness and completeness of the trial borings shown in the cross section.
82. The bidder should employ enough technically skilled persons including qualified Engineer at his own cost and risk for supervision of the work.

Signature of Contractor


Block Development Officer,
Rairangpur.

83. Grubbing out roots and clearing shrub jungles, if any, will be done by the bidder for which no extra payment will be made.
84. The bidder is entitled to be paid only at the rates quoted by him for execution of the item of work. If the bidder is required to pay for any ancillary work for completion of the item of work confirming to the contract specification it will be constructed as his exclusive responsibility for specific performance of the contract and nothing extra over and above the agreement rates will be paid.
85. The bidder shall engage local labourers on priority basis during execution of work.
86. No claim whatsoever will be entertained for any damage caused to work during supply of water in Canal.
87. The bidder has to make good damages caused to canal banks for carriage of materials at his own cost.
88. Any damage or loss of the materials during carriage and the cost thereof are to be borne by the bidder.
89. All fittings for doors and windows if supplied by the bidder should be of best quality and should be got approved by the Engineer-in-charge before they are used in the work.
90. No claim will be entertained in respect of difficulties due to sand blowing met with during sinking of wells.
91. No part of the bearing for the superstructure shall be allowed to rest on the noses of the piers.
92. The use of mild steel roller and pins be permitted provided these are made either or gauge-III or IV steel in accordance with I.R.C. specification M.S. roller and pins of forge metal alternatively be turned from Railway carriage and wagon axles (these may be designed according to the formula). $P=D^2 32$ where 'P' is the permissible load in tones per inch length or roller and 'D' is the diameter of the roller in inches.
93. Locks and groves shall be provided in the bearings so as prevent them from getting out of the alignment.
94. For proper maintenance of metallic bearings suitably designed boxes having necessary grease for lubrication and permitting easy access the bearings shall be provided to prevent dust or other foreign materials getting into the Bearings.
95. Sliding plate bearing shall normally be form anyone metal and combination of plates of different metals which are likely to result inaction shall not be permitted. Copper plate pressed in between steel plates will not be allowed.

96. ADDITIONAL CLAUSE TO BE INCLUDED IN THE FAIR WAGE (SAID CLAUSE 34 OF CONDITIONS OF CONTRACT) INTRODUCED IN G.O 44 VIIS. 13/62 DATED 20.2.1995.

1.a) Under the provision of the Minimum Wages Act, 1948 and the Minimum Wages (Central) Rules 1950, the Contractor is bound to allow or cause to be allowed to the labourer directly or indirectly employed on the works one day rest for six days of continuous work and pay wages at the same rates as for duty in the event of default, the Block Development Officer concerned shall have the right to deduct the sums not paid on account of wages for weekly holidays to any labour and pay the same to the persons entitles thereto form any money due to the Contractor.

Signature of Contractor


Block Development Officer,
Rairangpur.

b) The contractor shall at his own expense provide or arrange for the provision of foot wear for any labourer doing cement mixing work and black topping of roads. The contractor has undertaken to do so, Government shall be entitled to provide the same and recover the cost from the Contractor.

2. Pay

(i) In case of delivery:

Leave pay during maternity leave will be at the rate of the worker's average daily earnings calculated on the total wages earned on the days the full time work was done during a period of three months immediately preceding the date on which the given notice that she expects to be confined or at the rate of twelve annas a day whichever is greater.

(ii) In case of miscarriage:

Leave pay at the rate of average daily earning calculated on the total wages earned on the days when full time work was done during a period of three months immediately preceding the date of such miscarriage.

(iii) Conditions for the grant of maternity:

Maternity leave benefit shall be admissible to women unless she has been employed for a total period not less than 6 months immediately preceding the date on which she proceeds on leave.

This will apply only to work places which may continue a year or more.

97. Inspection and Quality Control Tests.


Except as otherwise provided in hereof all materials and workmanship, if not otherwise designated by the specifications, shall be subject to Inspections, examination and quality control test by the Engineer-in-charge at any and all times during manufacture and/ or constructions and at any / all places where such manufacture or constructions are carried on. The Engineer-in-charge shall have the right to reject defective material and workmanship or require its corrections. Rejected workmanship shall be satisfactorily replaced with proper material without charge thereof and the Contractor shall properly segregate and remove the rejected material from the premises. If the Contractor fails to proceed at once with the replacement of the rejected material and/or the construction of defective workmanship, the Engineer-in-charge may replace such material and / or correct such workmanship and charge the cost thereof to the Contractor.

98. Substantial still photographs and / or Video recording be done by the bidder at his own cost prior to execution, during execution, and after completion of the work as per the direction of the Engineer-in-charge and the C.Ds./print outs thereof should be accompanied by the R/A bills and Final bill.

99. Compensation on account of idle labour and / or idle machinery for any reason whatsoever shall not be allowed but extension of time shall be considered if the hindrance is not attributable to the bidder.

100. In the event of non-achievement of proportionate progress confirming to works Department Circular No. 24716 dt. 24.12.2005 incorporated in clause 51 of DTCN instant / appropriate action shall be initiated against the bidder for recession of the contract under Clause 2(b) of the F2 agreement on payment liability of the admissible amount from him.

Signature of Contractor


Block Development Officer,
Rairangpur.

101. Bidders are also required to go through each clause of PWD from F2 Agreement carefully in addition to the clauses mentioned herein before bidding. The clauses contained in the DTCN from part and parcel of the Agreement and also binding upon the bidder **Force Majeure**.

102. Should failure in performance of any part of this deed/ subsequent agreement arises from war, insurrection, restraint imposed by Government, Act of Legislature of other authority, stoppage of hindrance in the supply of raw materials, or fuel, explosion, accident, strike, riot, lock-out or other disorganization of labour or transport, break down of machine, flood, fire, act of God, or any inevitable or unforeseen event beyond human control directly or indirectly interfering with the supply of stores or from any cause which may be a reasonable ground for an extension of time, the competent authority will allow such additional time as he considers to be justified in the circumstances of the case. No compensation will be payable to the bidder for any loss incurred by him due to these reasons.

103. The royalty of materials will be recovered from the work bills as detailed herein below in case of failure of production of proper money receipt from Revenue Department. The rates have been extracted from Orissa Minor Minerals Concession Rules 2004. Any amendment / modification on the following rates shall prevail.

MATERIALS	RATE (In Rupees)	UNIT
1. Sand filling	35.00	Each Cum
2. Hard fine	35.00	Each Cum
3. Hard granite metal I.R.C. Gr. II	130.00	Each Cum
4. Hard granite metal I.R.C. Gr. III	130.00	Each Cum
5. Hard stone metal	130.00	Each Cum
6. Hard stone boulder	130.00	Each Cum
7. Hard granite boulder	130.00	Each Cum
8. Moorum	35.00	Each Cum
9. Hard granite chips	130.00	Each Cum

104. The authority competent to accept the bid reserves the right of accepting the bid for the whole work for a distinct part of it or distributing the work between one more bidders.

105. For the purpose of jurisdiction in the event of any dispute the contract would be deemed to have been entered into within the State of Orissa and it is agreed that neither party to the contract will be competent to bring a suit in regard to the matter by this contract at ny place outside the State of Orissa.

106. The Department reserves the right to verify all statements/credentials furnished along with the bid and to inspect the bidder's establishment/workshop so as to evaluate the bidder's capacity to execute the work and also reserves the right to defer/reject/accept any or all the Bids without assigning any reason whatsoever. The Department shall in no way be held liable for such action nor will make any obligation to inform the bidder the ground for the same.

Signature of Contractor


Block Development Officer,
Ralrangpur.

107. **IMPLEMENTATION OF THE BUILDING AND OTHER CONSTN. WORKERS (R.E. & CS) ACT 1996 AND THE BUILDING AND OTHER CONSTN. WORKERS WELAFARE CESS ACT 1996.**

- a) The Government of India in the Ministry of Labour & Employment has enacted the building and other constn. Workers (Regulation of Employment and Conditions of Service) Act, 1996 with the objective of regulating the Employment and Conditions of Service of the Building and other constn. Workers and to provide their safety, health and welfare measures. The Government of Orissa with a view to enforce the provisions of the Building and Other constn. Workers (Regulation of Employment and Conditions of Service) Act, 1996 have formulated rules namely the Orissa Building and other Constn. Workers (Regulation of Employment and conditions of service) Rules 2002 and this has been published in the Orissa Gazette vide Government Notification No. 9174-LE dt. 02.08.2002.
- b) In accordance with the provision under section 3(1) of the Building and other construction workers welfare cess Act, 1996, the State Government have been pleased to order for collection of cess @ 1% of the cost of construction incurred by and employer & builder which shall exclude the cost of land and any other compensation paid or payable to a worker or his kin under the workman compensation Act 1923.
- c) In the light the decision taken by the Government to enforce the provision of the building and other constn, workers welfare cess 1996 it is ordered that :-
All Government Departments, Public sector undertakings and other Government Departmental agencies/bodies carrying out any buildings or other construction works which are covered under section 2(1)(d) of the Building and other construction workers (RE & CS) Act, 1996 shall pay 1% of the amount of the cost approved as per the tender notification. This amount will be deducted from the bill at the time of marking payment to the contractors and such amount shall be remitted by way of account payee cheque in favour of the Orissa Building and other construction workers Welfare Board within 30 days making payment along with a forwarding letter addressed to the Secetary-cumChief Executive Officer, the Orissa Building and other Construction workers Welfare Board, Office of the Labour Commissioner, Orissa, Bhubaneswar.

108. QUALITY CONTROL AND MONITORING UNDER DOWR.


The quality Control, Monitoring & Assessment works shall be carried out in accordance with the guidelines contained in the codes and publications of the B.I.S. (Appended) on different subjects read with relevant provisions of any technical manual issued by the department from time to time on the subject of standards and quality of different items of work. The Quality Control and Monitoring Organisations in DOWR is proposed to be a 2 tier one as described below.

Quality Control, Monitoring and Assurance by Implementing Agency (IA) & Project Implementing Unit (PIU)

I.A. is the contractor executing the work.

P.I.U. covers the field Executive Engineer, E.E. Quantity Control Division of the Project, CRO, Quality Control Division for territorial field works.

Signature of Contractor


Block Development Officer,
Rairangpur

ii. State Quality Monitoring cell (SQMC)

Engineer-in-Chief, (P & D) shall be the Chairman of SQMC. The following may be the member of the Cell.

- i) C.E., Designs & Research (to be renamed as C.E., Designs, Research & Quality Control - Member
- ii) C.E., Minor Irrigation - Member.
- iii) Director, Research (to be renamed as Director, Research & Quality Control - Nodal Officer.

SQMC with the held of experts from the following fields will go ahead with the mission.

a) Retired Engineers of the State Government.

b) Retired Experts from Govt. Engineering Colleges.

A panel of experts is to be formed and approved by the Government. Their service will be utilized as and when required on day-to-day basis by the Director, Research and Quality Control the nodal officer of the Cell.

I. a. Quality Control & Assurance by the Implementing Agency (Contractor)

It shall be the prime responsibility of the implementing Agency (the contractor) to ensure the quality of the materials to be used, quality of works to be executed as well as the quality of the finished products as per the specification.

The I.A. (for works costing Rs. 10.00 lakhs and above shall set up a field QC laboratory and appoint qualified personnel for testing of samples.

The I.A. will be responsible for safety in construction, which includes watching lightening insurance, health and environmental protection.

The I.A. shall produce test results/test certificate of the materials used in the works and test results of concrete and of the finished products as specified. The test results/certificates are to be scrutinized by the E.E. before clearing the bills.

The I.A. shall take up the quality control tests i.e. tests for fine aggregate/course aggregate etc. in the approved laboratory of his own cost & produce the test results.

In case of any doubt or in absence of the test certificate for the quality of materials, the Engineer-in-charge of the work may take up the test at Laboratories of either Central Govt./State Govt./ PSUs/Govt. Institutes or priGSTe firms located nearby. The priGSTe Firms are to be approved by the Government for various works. The expense of tests is to be borne by the I.A.

The work bills may be passed and paid if the quality criteria are full satisfied.

109. MINIMUM QUALIFYING CRITERIA.

a) Satisfactorily completed (not less than of the original contract value) as a prime contractor i.e. value not less than Rs. _____ Lakhs at _____ price level (Attested copy of certificate of authenticity is to be enclosed from the concerned Block Development Officer) Weightage of 10% per year shall be given on cost of completed works of previous year to bring them to _____ price level. Failure to submit proof in support will result non responsive of the tender.

b) The bidder should produce documentary evidence regarding availability of the following machineries and equipments in working condition required for execution of the work (either owned in his name or obtained on hire purchase scheme or by hiring from the reputed firms/contractor's firms).

Signature of Contractor



Block Development Officer,
Rairangpur.

if the machineries are to be procured for specific period for completion of the work on lease/rental basis than a copy of registered MOU must attached. Failure to attach the documentary evidence in support of availability of required machineries may result in non responsive for tender.

Sl. No.	Name of the equipment	Number required
1.	Tipper / Truck /Tractor	1 nos.
2.	Concrete Mixture	1 nos.
3.	Concrete Vibrator (plate with needle type)	1 nos.
4.	Water tanker	1 nos.
5.	Rigid centering & Shuttering Plates (Steel / Iron / Wood)	50 Sqm.

- d) Sub-contractors experience and resources shall not be taken into account in determining the bidders compliance with the qualifying criteria.

Signature of Contractor


Block Development Officer,
Rairangpur.

ANNEXURE - 'A'

DESCRIPTION OF WORK PUT TO BID

Amount In Rupees.

Sl. No.	Name of the Work	Value of work.	Addl. Place of sale & receipt.	Security deposit	Cost of bid document	Period of Completion	Class of bidder entitled for the bid
1	2	3	4	5	6	7	8

Signature of Contractor


Block Development Officer,
Rairangpur.


ANNEXURE – 'B'

Undertaking to pay minimum wages to the labourers.

(Refer clause 41 read with clause 96 of DTCN.)

I undertake to pay minimum wages per day as admissible to the labourers engaged by me. In case the Block Development Officer is satisfied that the minimum wages conforming to the Minimum Wages Act have not been paid, the differential amount, of which the decision of the Block Development Officer shall be final, conclusive and binding upon me, shall also become deductible from the bill(s) that has / have become due or may become due to me, for payment to the labourers who were under paid, in such manner as he B.D.O. may deem proper. The disbursement of minimum wages to the labourers means and includes the payment in shape of Cash / Food grain or both on proper acknowledgement in the Muster Rolls maintained by me. I further undertake to be accountable to the Department in accordance with the text of Clause 87 of DTCN in the event of works taken up under food for Programme work.

Signature of Contractor


**Block Development Officer,
Rairangpur.**


ANNEXURE – 'C'

Certificate of No Relationship as per Clause 52 of DTCN.

I/we do hereby certify that I/We am / are not related to any officer of Block Office of the rank of Asst. Engineer and above I/We am/are aware that if facts subsequently proved to be false my/our contract will be rescinded with forfeiture of EMD & Security Deposit and I/We shall be liable to make good the loss or damages resulting from such cancellation.

I/ We also note that, non-submission of this certificate may render my/our tender liable for rejection.

Signature of Contractor


Block Development Officer,
Rairangpur.

ANNEXURE – 'D'

To

THE BLOCK DEVELOPMENT OFFICER
RAIRANGPUR, MAYURBHANJ.

Sub:- List of T & P/Machinerles/Vehicles.

Sir,

As required under Clause No.111 of the Detailed Tender Call Notice, I am to furnish herewith the above information as mentioned below so as assess my capability to execute the work.

List of T & P /Machinerles/Vehicles

Sl. No.	Details of T & P/ Machinerles / Vehicles the bidder owns	Make	Year of manufacture	Number (Unit)
1				
2				
3				
4				
5				

Yours faithfully

Signature of the Bidder



Block Development Officer,
Rairangpur.

Signature of Contractor

ANNEXURE – 'E'

INFORMATION REGARDING CURRENT LITIGATION, DEBARRING
EXPELLING OF TENDERER OR ABANDONMENT OF WORK BY THE
TENDERER

1. a) Is the tenderer currently involved in any litigation relating to the works. Yes/ NO
b) If Yes: give details:
2. a) Has the tenderer or any of its Constituent partners been debarred/ Expelled during the last 5 years. Yes/No
- 3.a) Has the tenderer or any of its Constituent partners failed to Perform on any contract work in India during the last 5 years.
b) If yes , give details:

Note:

If any information in this schedule is found to be incorrect or concealed, qualification application will summarily be rejected.

Signature of Tenderer

ANNEXURE – 'G'

AFFIDAVIT

1. The undersigned do hereby certify that all the statements made in the required attachments are true and correct.
2. The undersigned also hereby certifies that neither my / our firm/ company/ individuals _____ nor any of its constituent partners have abandoned any road/bridge/Irrigation/ Buildings or other project work in India nor any contract awarded to us for such works have been rescinded during the last five years prior to the date of this bid.
3. The undersigned hereby authorize(s) and request(s) any bank, person, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Department to verify this statement or regarding my (our) competency and general reputation.
4. The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Department.

(Signature of Tenderer)

Title of Officer

Name of Firm


Block Development Officer,
Rairangpur.

BIDDER CONTACT ADDRESS FILLING
MANDATORY

1. Name.
2. Address.
3. e-mail ID.
4. Mobile No.
5. GSTIN No.
6. PAN No.


Signature of the Bidder



Block Development Officer,
Rairangpur.

INSTRUCTIONS TO BIDDER

1. Only "percentage quoted bid" of the bidder shall be considered.
2. Percentage quoted by the bidder shall be accurately filled in words and figure.
3. If any discrepancy is found between words and figure, rate quoted in words shall be taken as correct.
4. If any discrepancy is found in the percentage quoted in "percentage excess or less" and "Total amount quoted by the bidder" than the percentage shall be taken as accordingly the bid price shall be corrected which would be binding upon the bidder.
5. If the bidder quoted the percentage without mentioning excess or less and not supported with corresponding amount will be treated as excess.
6. The bidder shall write the percentage in excess or less up to one decimal point only. If the bidder writes the percentage up to two or more decimal point 1st decimal point shall only be considered without rounding off.
7. Where is the bidder omitted to quote the percentage either in words or figure the officer opening the bid should record the omission and the bid will be rejected.


Block Development Officer,
Rairangpur.

(For Office use only.)

Number of over writings :
Number of corrections :
Number of omissions :
EMD :
GST :
PAN CARD :
NRC :
Affidavit :
Labour License :

Sold on Payment of Rs.....Rupees..... only in
shape of Demand draft towards cost of tender paper vide M/R
No.....Dt.....


Block Development Officer
Rairangpur

B.O.Q. FOR THE WORK :-


**Construction of ACR Building at Sundhol Govt. Upper Primary School
Badmouda G.P.**

No	Item Description	Unit	Quantity	Rate	Amount
1)	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	55.57	₹ 279.63	₹ 15,540.00
2)	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	62.01	₹ 899.72	₹ 55,794.00
3)	Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance, royalty of materials etc complete	Cum	18.30	₹ 5,880.35	₹ 1,07,604.00
4)	R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	33.70	₹ 6,123.48	₹ 2,06,334.00
5)	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	33.02	₹ 6,921.60	₹ 2,28,562.00
6)	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
(i)	R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	44.56	₹ 247.80	₹ 11,042.00
(ii)	R.C.C. beam, girder and bressmer etc.	Sqm	75.46	₹ 1,192.53	₹ 89,986.00
(iii)	R.C.C. Lintel	Sqm	19.98	₹ 571.46	₹ 11,418.00
)	Roof Slab & Chhaja	Sqm	85.87	₹ 754.55	₹ 64,795.00
7)	Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
	Foundation & Plinth	Cum	10.31	₹ 5,569.54	₹ 57,412.00
	Superstructure	Cum	23.99	₹ 5,602.54	₹ 1,34,417.00
8)	6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slury treatment including all cost conveyance & royalty etc complete.	Sqm	82.21	₹ 179.50	₹ 14,757.00
9)	12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	167.23	₹ 191.89	₹ 32,090.00
10)	16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	126.72	₹ 276.13	₹ 34,990.00
11)	Provision for M. S. Shutter	Kg	435.75	₹ 120.00	₹ 52,290.00
12)	Labour for fitting & fixing of door & windows	Sqm	13.49	₹ 112.97	₹ 1,524.00

3)	Providing fitting & fixing vetrified Tiles in floor of size 600mmX600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1 4) and filling joints with white cement of approved quality including cost of all material, labour T&P etc required for the work all complete. (Data for 10Sqm) (Vide A/R 2012 in Items of other building 1-(B) for New work of S/R-2012	Sqm	74.25	1083.26	₹ 80,433.00
4)	Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	7.34	1578.93	11588.00
5)	Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	17.09	1321.95	22597.00
6)	Wall painting two coat with plastic emulsion paint over a coat of primer after finising wall surface of walls with acrylic wall putty (water based) of approved make and finished smooth & even surface to received painting including cost of scaffolding charges with cost of all materials labour etc complete.				
	(A) Ground Floor	Sqm	173.32	₹ 176.29	₹ 30,555.00
17)	Priming 1 coat with any approved primer incl.cost of primer & labour all complete				
	(A) Ground Floor	Sqm	376.16	₹ 74.06	₹ 27,858.00
18)	Distempering two coats with any approved shade including cost of distemper incl all cost etc. compl.				
	(A) Ground Floor	Sqm	173.94	₹ 89.69	₹ 15,600.00
19)	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm				
	(A) Ground Floor	Sqm	112.69	₹ 107.86	₹ 12,155.00
20)	Painting Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.				
	(A) Ground Floor	Sqm	26.09	₹ 224.52	₹ 5,858.00
21)	20mm Thick C.P. for grading work in C. M. (1 : 6) in roof slab including cost of carriage, roylity etc. compl.				
	(A) Ground Floor	Sqm	88.84	₹ 300.61	₹ 26,705.00

22)	Supplying, fitting and fixing of Stainless Steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipes with Balustrade of size 32mm x32mmx 2mm @ 0.90m c/c and stainless square pipe bracing of 32mm x 32mmx 2mm in three rows in stair case as per approved design and specifications buffing, polishing including cost, carriage,royalty etc complete. (Data for 3.26 Rmt) Revised A/ R(Building) -2012, Item no - 11.				
(A) Ground Floor		Rmt.	12.40	₹ 3,015.75	₹ 37,395.00
				Total Amount for B.O.Q.=	₹ 13,89,299.00

(Rupees Thirteen Lakhs Eighty nine Thousand Two Hundred Ninty Nine)only


Assistant Engineer,
Rairangpur Block


Assistant Executive Engineer,
Rairangpur Block


Block Development Officer,
Rairangpur Block

My quoted Rate is%()
excess over/ less than/ equal to the above tendered value.

- Note:-
- 1) The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate. Any conditional rate quoted is not accepted.
 - 2) Strikeover on the rate quoted is liable to rejection.
 - 3) Percentage rate quoted should be within 2(Two) digit after decimal point.
 - 4) Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.
 - 5)

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer

B.O.Q. FOR THE WORK :-

Construction of ACR Building at Badmouda Govt. UGUP School in Badmouda G.P.

No	Item Description	Unit	Quantity	Rate	Amount
1)	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	55.57	₹ 279.63	₹ 15,540.00
2)	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	62.01	₹ 899.72	₹ 55,794.00
3)	Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance, royalty of materials etc complete	Cum	18.30	₹ 5,880.35	₹ 1,07,604.00
4)	R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	33.70	₹ 6,123.48	₹ 2,06,334.00
5)	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	33.02	₹ 6,921.60	₹ 2,28,562.00
6)	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
(i)	R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	44.56	₹ 247.80	₹ 11,042.00
(ii)	R.C.C. beam, girder and bressmer etc.	Sqm	75.46	₹ 1,192.53	₹ 89,986.00
iii)	R.C.C. Lintel	Sqm	19.98	₹ 571.46	₹ 11,418.00
7)	Roof Slab & Chhaja	Sqm	85.87	₹ 754.55	₹ 64,795.00
7)	Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
	Foundation & Plinth	Cum	10.31	₹ 5,569.54	₹ 57,412.00
	Superstructure	Cum	23.99	₹ 5,602.54	₹ 1,34,417.00
8)	6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slurry treatment including all cost conveyance & royalty etc complete.	Sqm	82.21	₹ 179.50	₹ 14,757.00
9)	12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	167.23	₹ 191.89	₹ 32,090.00
10)	16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	126.72	₹ 276.13	₹ 34,990.00
11)	Provision for M. S. Shutter	Kg	435.75	₹ 120.00	₹ 52,290.00
12)	Labour for fitting & fixing of door & windows	Sqm	13.49	₹ 112.97	₹ 1,524.00

3)	Providing fitting & fixing vetrified Tiles in floor of size 600mmX600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1 4) and filling joints with white cement of approved quality including cost of all material, labour T&P etc required for the work all complete (Data for 10Sqm) (Vide A/R 2012 in Items of other building 1-(B) for New work of S/R-2012	Sqm	74.25	1083.26	₹ 80,433.00
4)	Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	7.34	1578.93	11588.00
5)	Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	17.09	1321.95	22597.00
6)	Wall painting two coat with plastic emulsion paint over a coat of primer after finising wall surface of walls with acrylic wall putty (water based) of approved make and finished smooth & even surface to received painting including cost of scaffolding charges with cost of all materials labour etc complete.				
	(A) Ground Floor	Sqm	173.32	₹ 176.29	₹ 30,555.00
17)	Priming 1 coat with any approved primer incl.cost of primer & labour all complete				
	(A) Ground Floor	Sqm	376.16	₹ 74.06	₹ 27,858.00
18)	Distempering two coats with any approved shade including cost of distemper incl all cost etc. compl.				
	(A) Ground Floor	Sqm	173.94	₹ 89.69	₹ 15,600.00
19)	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm				
	(A) Ground Floor	Sqm	112.69	₹ 107.86	₹ 12,155.00
20)	Painting Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.				
	(A) Ground Floor	Sqm	26.09	₹ 224.52	₹ 5,858.00
21)	20mm Thick C.P. for grading work in C. M. (1 : 6) in roof slab including cost of carriage, roylity etc. compl.				
	(A) Ground Floor	Sqm	88.84	₹ 300.61	₹ 26,705.00

2) Supplying, fitting and fixing of Stainless Steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipes with Balustrade of size 32mm x32mmx 2mm @ 0.90m c/c and stainless square pipe bracing of 32mm x 32mmx 2mm in three rows in stair case as per approved design and specifications buffing, polishing including cost, carriage, royalty etc complete. { Data for 3.26 Rmt } Revised A/ R(Building) -2012, Item no - 11				
(A) Ground Floor	Rmt.	12.40	₹ 3,015.75	₹ 37,395.00
	Total Amount for B.O.Q.=			₹ 13,89,299.00

(Rupees Thirteen Lakhs Eighty nine Thousand Two Hundred Ninty Nine)only


Assistant Engineer,
Rairangpur Block


Assistant Executive Engineer,
Rairangpur Block


Block Development Officer,
Rairangpur Block

My quoted Rate is% ()
excess over/ less than/ equal to the above tendered value.

- Note:-
- 1) The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate. Any conditional rate quoted is not accepted.
 - 2) Strikeover on the rate quoted is liable to rejection.
 - 3) Percentage rate quoted should be within 2(Two) digit after decimal point.
 - 4) Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.
 - 5)

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer

TENDER SCHEDULE

" CONSTRUCTION OF KITCHEN -CUM-DINING HALL AT GORUMAHISANI HIGH SCHOOL

Estimated cost	Rs 10,00,000.00
Tender amount	Rs 7,73,869.00
Earnest Money to be Deposited	Rs 7739.00
Cost of Tender Paper	Rs 4000.00
Class of Contractor	D' & 'C'
Last Date of Receipt of Tender Paper	
Date of Opening of Tender Paper	
Time Required for Completion of work	

Abstract

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil within 50 met initial lead and 1.5 met lift including dressing and levelling the foundation bed....etc	100 cum	19.859	276.89	5416.00
2	Sand filling in foundation and plinth with well watered and and ramming ..etc	Cum	22.618	777.22	17579.00
3	PCC (1:3:6) using 40 mm size CBHG metal in foundation and base including cost conveyance royalty ..etc	Cum	4.986	29917.00	29917.00
4	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	Cum	9.438	4470.41	42190.00
5	RCC M20 using 12mm size C.B.H.G chips etc incl cost of all materials & Labours:-				
	a-Columns	Cum	3.888	6787.52	26390.00
	b-Plinth Beam	Sqm	1.500	7658.50	11488.00
	c-Column / Beam	Sqm	3.675	18330.02	67363.00
	d-Lintel Beam	Sqm	1.350	14457.43	19518.00
	e-Roof Slab	Sqm	6.336	13969.48	88516.00
6	Supplying, fitting, fixing & placing Uncoated HYSD bar reinforcement complete.	Qtl	15.07	8311.78	125295.00
7	Brick work with FLY ASH. Brick having crushing strength between 35 Kg/cm ² to 149 Kg/cm ² in C.M. (1 : 6) in super structure including cost, carriage and royalty etc.	Cum	17.18	4470.41	76779.00

8	25mm thick greading concrete (1:2:2) on roof slab with 6 mm size hbg chips for new work	Sqm	52.14	399.51	20831.00
9	6 mm thick Cement Plaster with C.M (1:4) on ceiling including all cost, conveyance & royalty etc. complete. A/R, Page-109, SI - (26)	Sqm	92.17	182.46	16816.00
10	16 mm thick Cement Plaster with CM (1:6) including all cost, conveyance & royalty etc. complete.	Sqm	95.58	280.74	26834.00
11	12 mm thick CP with CM (1:6) including all cost, conveyance & royalty etc all complete. A/R, Page-103, SI - (4)	sqm	104.40	195.35	20395.00
12	Supplying fitting fixing of M S door & windowetc	Kg	705.00	103.30	72828.00
13	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, SI.(17)	Sqm	40.60	1208.36	49060.00
14	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, SI.(17)	Sqm	5.45	1344.01	7318.00
15	Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.	Sqm	292.15	83.75	24467.00
16	Distempering two coats to wall with distemper of approved shade on new work including all cost etc complete.	Sqm	95.58	90.59	8658.00
17	Finishing wall painting two coats with any approved weather seal coat paint including all cost, carriage,royalty etc co	Sqm	104.40	107.79	11253.00
18	Painting two coat with any approved paint on Iron work over a coat of priming including all cost,carriage,royalty etc complete.	Sqm	18.72	264.84	4958.00

19	Total =		Rs	773869.00
----	---------	--	----	-----------

(Rupees seven lakhs seventy three thousand eight hundred sixty nine) only.


 Asst. Engineer
 Rairangpur Block


 Asst. Executive Engineer
 Rairangpur Block


 Block Development Officer
 Rairangpur

Rate quoted in terms of % (percentage) less or excess over the value of the tender amount as given above (Both in words and figure in details) The Percentage less or excess will be up to two decimal point only.

- (a) In Figures% Excess/Less
 (b) In Words% Excess/Less

N.B. - Percentage of excess or Less to be quoted both in words and figures.

Singature of the Contractor

TENDER SCHEDULE

" CONSTRUCTION OF KITCHEN -CUM-DINING HALL AT KGBV GORUMAHISANI

Estimated cost	Rs 10,00,000.00
Tender amount	Rs 7,73,869.00
Earnest Money to be Deposited	Rs 7739.00
Cost of Tender Paper	Rs 4000.00
Class of Contractor	D' & 'C'
Last Date of Receipt of Tender Paper	
Date of Opening of Tender Paper	
Time Required for Completion of work	

Abstract

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil withen 50 met initial lead and 1.5 met lift including dressing and levelling the foundation bed....etc	100 cum	19.859	276.89	5416.00
2	Sand filling in foundation and plinth with well watered and and ramming ..etc	Cum	22.618	777.22	17579.00
3	PCC (1:3:6) using 40 mm size CBHG metal in foundation and base including cost conveyance royalty ..etc	Cum	4.986	29917.00	29917.00
4	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	Cum	9.438	4470.41	42190.00
5	RCC M20 using 12mm size C.B.H.G chips etc incl cost of all materials & Labours:-				
	a-Columns	Cum	3.888	6787.52	26390.00
	b-Plinth Beam	Sqm	1.500	7658.50	11488.00
	c-Column / Beam	Sqm	3.675	18330.02	67363.00
	d-Lintel Beam	Sqm	1.350	14457.43	19518.00
	e-Roof Slab	Sqm	6.336	13969.48	88516.00
6	Supplying, fitting, fixing & placing Uncoated HYSD bar reinforcement complete.	Qtl	15.07	8311.78	125295.00
7	Brick work with FLY ASH. Brick having crushing strength between 35 Kg/cm ² to 149 Kg/cm ² in C.M. (1 : 6) in super structure including cost, carriage and royalty etc.	Cum	17.18	4470.41	76779.00

8	25mm thick greading concrete (1:2:2) on roof slab with 6 mm size hbg chips for new work	Sqm	52.14	399.51	20831.00
9	6 mm thick Cement Plaster with C.M (1:4) on ceiling including all cost, conveyance & royalty etc. complete. A/R, Page-109, SI - (26)	Sqm	92.17	182.46	16816.00
10	16 mm thick Cement Plaster with CM (1:6) including all cost, conveyance & royalty etc. complete.	Sqm	95.58	280.74	26834.00
11	12 mm thick CP with CM (1:6) including all cost, conveyance & royalty etc all complete. A/R, Page-103, SI - (4)	sqm	104.40	195.35	20395.00
12	Supplying fitting fixing of M S door & windowetc	Kg	705.00	103.30	72828.00
13	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, SI.(17)	Sqm	40.60	1208.36	49060.00
14	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, SI.(17)	Sqm	5.45	1344.01	7318.00
15	Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.	Sqm	292.15	83.75	24467.00
16	Distempering two coats to wall with distemper of approved shade on new work including all cost etc complete.	Sqm	95.58	90.59	8658.00
17	Finishing wall painting two coats with any approved weather seal coat paint including all cost, carriage,royalty etc co	Sqm	104.40	107.79	11253.00
18	Painting two coat with any approved paint on Iron work over a coat of priming including all cost,carriage,royalty etc omplete.	Sqm	18.72	264.84	4958.00

19	Total =		Rs	773869.00
----	---------	--	----	-----------

(Rupees seven lakhs seventy three thousand eight hundred sixty nine) only.


 Asst. Engineer
 Rairangpur Block


 Asst. Executive Engineer
 Rairangpur Block


 Block Development Officer
 Rairangpur

Rate quoted in terms of % (percentage) less or excess over the value of the tender amount as given above (Both in words and figure in details) The Percentage less or excess will be up to two decimal point only.

- (a) In Figures% Excess/Less
 (b) In Words% Excess/Less

N.B. - Percentage of excess or Less to be quoted both in words and figures.

Singature of the Contractor

B.O.Q. FOR THE WORK :-


**Construction of ACR Building at Jambani Govt. Primary School in
Madarshanpur G.P.**

Sl. No.	Item Description	Unit	Quantity	Rate	Amount
	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	51.14	₹ 279.63	₹ 14,301.00
	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	59.50	₹ 1,029.92	₹ 61,284.00
	Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance, royalty of materials etc complete	Cum	17.30	₹ 6,005.34	₹ 103,887.00
	R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	36.16	₹ 6,240.66	₹ 225,689.00
	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	35.44	₹ 6,921.60	₹ 245,308.00
	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
i)	R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	43.45	₹ 247.80	₹ 10,766.00
ii)	R.C.C. beam, girder and bressmer etc.	Sqm	75.46	₹ 1,192.53	₹ 89,986.00
iii)	R.C.C. Lintel	Sqm	19.98	₹ 571.46	₹ 11,418.00
	Roof Slab & Chhaja	Sqm	85.41	₹ 754.55	₹ 64,446.00
7)	Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
	Foundation & Plinth	Cum	10.06	₹ 5,606.00	₹ 56,398.00
	Superstructure	Cum	23.03	₹ 5,639.00	₹ 129,839.00
3)	6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slurry treatment including all cost conveyance & royalty etc complete.	Sqm	77.43	₹ 180.47	₹ 13,974.00
9)	12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	160.33	₹ 193.84	₹ 31,078.00
0)	16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	120.99	₹ 278.48	₹ 33,692.00
1)	Provision for M. S. Shutter	Kg	435.75	₹ 120.00	₹ 52,290.00
12)	Labour for fitting & fixing of door & windows	Sqm	13.49	₹ 112.97	₹ 1,524.00

Providing fitting & fixing vetrified Tiles in floor of size 600mmX600mm of approved make confirming to IS:13755 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all material, labour T&P etc required for the work all complete. (Data for 10Sqm) (Vide A/R 2012 in Items of other building 1-(B) for New work of S/R-2012	Sqm	70.01	1096.28	₹ 76,750.00
Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	6.57	1591.95	10463.00
Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	17.09	1334.97	22819.00
Wall painting two coat with plastic emulsion paint over a coat of primer after finising wall surface of walls with acrylic wall putty (water based) of approved make and finished smooth & even surface to received painting including cost of scaffolding charges with cost of all materials labour etc complete.				
(A) Ground Floor	Sqm	166.35	₹ 176.29	₹ 29,326.00
Priming 1 coat with any approved primer incl.cost of primer & labour all complete				
(A) Ground Floor	Sqm	358.74	₹ 74.06	₹ 26,569.00
Distempering two coats with any approved shade including cost of distemper incl all cost etc. compl.				
(A) Ground Floor	Sqm	166.35	₹ 89.69	₹ 14,920.00
Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm				
(A) Ground Floor	Sqm	112.69	₹ 107.86	₹ 12,155.00
Painting Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.				
(A) Ground Floor	Sqm	26.09	₹ 224.52	₹ 5,858.00
20mm Thick C.P. for grading work in C. M. (1 : 6) in roof slab including cost of carriage, roylity etc. compl.				
(A) Ground Floor	Sqm	84.10	₹ 303.34	₹ 25,511.00

22	Supplying, fitting and fixing of Stainless Steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipes with Balustrade of size 32mm x32mmx 2mm @ 0.90m c/c and stainless square pipe bracing of 32mm x 32mmx 2mm in three rows in stair case as per approved design and specifications buffing, polishing including cost, carriage,royalty etc complete. (Data for 3.26 Rmt) Revised A/ R(Building) - 2012, Item no - 11.				
	(A) Ground floor	Mtr	12.40	3015.75	37395.00
Total Amount for B.O.Q. =				Rs	1407646.00

(Rupees Fourteen Lakhs Seven Thousand Six Hundred Fourty - Six) only.

18/2/26

Junior Engineer
Rairangpur Block


Asst. Executive Engineer
Rairangpur Block

Handwritten initials
Block Development Officer
Rairangpur Block

My quoted Rate is% (*write in word*)
 excess over/ less than/ equal to the above tendered value.

Note:-

The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate.

Any conditional rate quoted is not accepted.

Strikeover on the rate quoted is liable to rejection.

Percentage rate quoted should be within 2(Two) digit after decimal point.

Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer

TENDER SCHEDULE

" CONSTRUCTION OF ADDL. CLASS ROOM AT GUHALDANGRI GOVT. PRIMARY SCHOOL"

Estimated cost	Rs 18,33,000.00
Tender amount	Rs 14,71,791.00
Earnest Money to be Deposited	Rs 14,718.00
Cost of Tender Paper	Rs 6000.00
Class of Contractor	D' & 'C'
Last Date of Receipt of Tender Paper	
Date of Opening of Tender Paper	
Time Required for Completion of work	

Abstract

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil withen 50 met initial lead and 1.5 met lift including dressing and levelling the foundation bed....etc	cum	48.19	276.89	13344.00
2	Sand filling in foundation and plinth with well watered and and ramming ..etc	Cum	86.71	974.47	84497.00
3	PCC (1:4:8) using 40 mm size CBHG metal in foundation and base including cost conveyance royalty ..etc	Cum	16.00	5956.79	95290.00
4	RCC M20 using 12mm size C.B.H.G chips etc incl cost of all materials & Labours:-	Cum	31.56	6345.25	199907.00
5	Supplying,fitting & placing uncoated HYSD bar reinforcement including all cost & carriage including labour charges,etc.	Qntl	28.40	8695.68	246522.00
6	Rigid and smooth centering ,shuttering for R.C.C. work including false works and dismantling them after casting.				
a	Plinth band	Sqm	62.64	248.85	16409.00
b	Column & Beam	Sqm	71.93	1191.58	84888.00
c	Lintel	Sqm	15.93	574.51	9152.00
d	celling beam	Sqm	16.46	574.51	9456.00
e	Chajja / Roof slab	Sqm	84.42	755.52	63777.00
7	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	Cum	13.13	4345.48	57056.00
8	Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.	Cum	27.15	4422.27	120082.00
9	6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chiping,etc.	Sqm	105.68	182.37	19273.00
10	12 mm thick cement plaster in C.M.(1:6) in external surface of wall,etc.	Sqm	125.60	195.57	24563.00

11	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall,etc.	Sqm	151.20	281.00	42487.00
13	Supplying fitting & fixing of MS Door & Window including all cost of material & Laour charges,etc.	Kg	358.15	120.00	42978.00
14	Supplying and fixing of G I pressed G I Door assembly with polymer power coated including the cost of all materials and fittings etc com.	sqm	4.41	7000.00	30870.00
15	Labour for fitting fixing of doors & windows etc	sqm	16.68	23.43	391.00
16	Fixing Vetrified tiles in floors,treads of steps and landing on 20 mm thick bed of cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labours T&P, rubbing and polishing etc all complete. (Data for 10 Sqm) (A/ R for other Bldg Items 2006, Sl.(2)	Sqm	76.60	1205.74	92359.00
17	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, Sl.(17)	Sqm	15.12	1340.37	20266.00
18	Fixing Chequered tiles in floors,treads of steps and landing on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 89, Sl.(16)	Sqm	12.42	1070.70	13298.00
19	Finishing surface of wall with Acrilic Wall Putty (Water based) of approved make and finished smooth and even surface to received painting including cost of puty all labour T&P etc complete.	Sqm	227.80	102.95	23452.00
20	Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.	Sqm	353.40	83.75	29596.00
21	Distempering two coats to wall with distemper of approved shade on new work including all cost etc complete.	Sqm	227.80	90.59	20636.00
22	Finishing wall painting two coats with any approved weather seal coat paint including all cost, carriage,royalty etc co	Sqm	125.60	107.79	13537.00
23	Painting two coat with any approved paint on Iron work over a coat of priming including all cost,carriage,royalty etc omplete.	Sqm	24.54	264.84	6499.00
24	2.5cm thick grading concrete(1:2:2) on roof slab with 4.7mm size h.g chips,etc.	Sqm	96.01	397.58	38169.00

25	Supplying, fitting and fixing of Stainless Steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipes with Balustrade of size 32mm x32mmx 2mm @ 0.90m c/c and stainless square pipe bracing of 32mm x 32mmx 2mm in three rowa in stair case as per approved design and specifications buffing, polishing including cost, carriage,royalty etc complete. (Data for 3.26 Rmt) Revised A/ R(Building) -2012, Item no - 11.	Mtr	17.55	3022.09	53037.00
Total =				Rs	1471791.00

(Rupees fourteen lakhs seventy one thousand seven hundred ninety one) only.


Asst. Engineer
Rairangpur Block


Asst. Executive Engineer
Rairangpur Block


Block Development Officer
Rairangpur

Rate quoted in terms of % (percentage) less or excess over the value of the tender amount as given above (Both in words and figure in details) The Percentage less or excess will be up to two decimal point only.

- (a) In Figures% Excess/Less
(b) In Words% Excess/Less

N.B. - Percentage of excess or Less to be quoted both in words and figures.

Singature of the Contractor


B.O.Q. FOR THE WORK :-

Construction of Kitchen shed at Palasbani Govt Pry School in Sanpakhna P.

Sl. No	Item Description	Unit	Quantity	Rate	Amount
1)	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	8.90	₹ 279.63	₹ 2,489.00
2)	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	4.02	₹ 834.62	₹ 3,353.00
3)	Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance, royalty of materials etc complete	Cum	2.27	₹ 5,786.61	₹ 13,134.00
4)	R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	5.74	₹ 6,035.60	₹ 34,640.00
5)	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	5.17	₹ 6,921.60	₹ 35,752.00
6)	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
7)	R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	5.48	₹ 247.80	₹ 1,358.00
8)	R.C.C. beam, girder and bressmer etc.	Sqm	16.61	₹ 1,192.53	₹ 19,804.00
9)	R.C.C. Lintel	Sqm	4.73	₹ 571.46	₹ 2,704.00
10)	Roof Slab & Chhaja	Sqm	13.50	₹ 754.55	₹ 10,189.00
11)	Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
	Foundation & Plinth	Cum	1.48	₹ 5,551.31	₹ 8,221.00
	Superstructure	Cum	5.20	₹ 5,584.31	₹ 29,054.00
12)	6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slurry treatment including all cost conveyance & royalty etc complete.	Sqm	9.59	₹ 179.01	₹ 1,717.00
13)	12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	39.81	₹ 190.91	₹ 7,601.00

0)	16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	27.01	₹ 274.96	₹ 7,427.00
1)	250Cm Thick A S flooring in C C (1 2 4) in roof slab using 12mm size h g c b Chips including cost of carriage, royality etc compl	Sqm	9 10	405 60	₹ 3,691.00
2)	Painting Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.	Sqm	15.85	₹ 224.52	₹ 3,559.00
3)	Painting one coat with any approved primer including cost of primer per 1 Sqm	Sqm	76.41	₹ 74.06	₹ 5,659.00
4)	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm	Sqm	76.41	₹ 107.86	₹ 8,242.00
5)	Provision for M. S. Shutter	Kg	231.00	₹ 120.00	₹ 27,720.00
				Total Amount for B.O.Q. =	₹ 2,26,314.00

(Rupees Two Lakhs Twenty six Thousand three Hundred Fourteen)only


Assistant Engineer,
Rairangpur Block


Assistant Executive Engineer,
Rairangpur Block


Block Development Officer,
Rairangpur Block

My quoted Rate is%
excess over/ less than/ equal to the above tendered value.

Note:-
The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate.
Any conditional rate quoted is not accepted.
Strikeover on the rate quoted is liable to rejection.
Percentage rate quoted should be within 2(Two) digit after decimal point.
Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer


B.O.Q. FOR THE WORK :-

Construction of Kitchen shed at Gadigan Govt Pry School in Sanpakhna G.P.

No	Item Description	Unit	Quantity	Rate	Amount
1)	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	8.90	₹ 279.63	₹ 2,489.00
2)	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	4.02	₹ 834.62	₹ 3,353.00
3)	Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance, royalty of materials etc complete	Cum	2.27	₹ 5,786.61	₹ 13,134.00
4)	R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	5.74	₹ 6,035.60	₹ 34,640.00
5)	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	5.17	₹ 6,921.60	₹ 35,752.00
6)	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
(i)	R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	5.48	₹ 247.80	₹ 1,358.00
(ii)	R.C.C. beam, girder and bressmer etc.	Sqm	16.61	₹ 1,192.53	₹ 19,804.00
(iii)	R.C.C. Lintel	Sqm	4.73	₹ 571.46	₹ 2,704.00
iv)	Roof Slab & Chhaja	Sqm	13.50	₹ 754.55	₹ 10,189.00
7)	Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
	Foundation & Plinth	Cum	1.48	₹ 5,551.31	₹ 8,221.00
	Superstructure	Cum	5.20	₹ 5,584.31	₹ 29,054.00
8)	6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slury treatment including all cost conveyance & royalty etc complete.	Sqm	9.59	₹ 179.01	₹ 1,717.00
9)	12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	39.81	₹ 190.91	₹ 7,601.00

10)	16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	27.01	₹ 274.96	₹ 7,427.00
11)	2 50Cm Thick A.S flooring in C C (1 : 2 : 4) in roof slab using 12mm size h. g.c.b. Chips including cost of carriage, royality etc compl	Sqm	9.10	405.60	₹ 3,691.00
12)	Painling Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.	Sqm	15.85	₹ 224.52	₹ 3,559.00
13)	Painting one coat with any approved primer including cost of primer per 1 Sqm	Sqm	76.41	₹ 74.06	₹ 5,659.00
14)	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm	Sqm	76.41	₹ 107.86	₹ 8,242.00
15)	Provision for M. S. Shutter	Kg	231.00	₹ 120.00	₹ 27,720.00
				Total Amount for B.O.Q. =	₹ 2,26,314.00

(Rupees Two Lakhs Twenty six Thousand three Hundred Fourteen)only


Assistant Engineer,
Rairangpur Block


Assistant Executive Engineer,
Rairangpur Block


Block Development Officer,
Rairangpur Block

My quoted Rate is% ()
excess over/ less than/ equal to the above tendered value.

Note:-

- 1) The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate. Any conditional rate quoted is not accepted.
- 2) Strikeover on the rate quoted is liable to rejection.
- 3) Percentage rate quoted should be within 2(Two) digit after decimal point.
- 4) Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.
- 5)

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer


B.O.Q. FOR THE WORK :-


Construction of Kitchen shed at Dhatkidihi Ashram School in Sudarshanpur G.P.

Sl No	Item Description	Unit	Quantity	Rate	Amount
1)	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	8.90	₹ 279.63	₹ 2,489.00
2)	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	4.02	₹ 1,029.92	₹ 4,137.00
3)	Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance; royalty of materials etc complete	Cum	2.27	₹ 6,005.34	₹ 13,630.00
4)	R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	5.74	₹ 6,240.66	₹ 35,817.00
5)	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	5.17	₹ 6,921.60	₹ 35,752.00
6)	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
(i)	R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	5.48	₹ 247.80	₹ 1,358.00
(ii)	R.C.C. beam, girder and bressmer etc.	Sqm	16.61	₹ 1,192.53	₹ 19,804.00
(iii)	R.C.C. Lintel	Sqm	4.73	₹ 571.46	₹ 2,704.00
iv)	Roof Slab & Chhaja	Sqm	13.50	₹ 754.55	₹ 10,189.00
7)	Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
	Foundation & Plinth	Cum	1.48	₹ 5,606.00	₹ 8,302.00
	Superstructure	Cum	5.20	₹ 5,639.00	₹ 29,339.00
8)	6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slurry treatment including all cost conveyance & royalty etc complete.	Sqm	9.59	₹ 180.47	₹ 1,731.00
9)	12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	39.81	₹ 193.84	₹ 7,717.00

10)	16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	27.01	₹ 278.48	₹ 7,522.00
11)	2.50Cm. Thick A.S. flooring in C. C. (1 :2 :4) in roof slab using 12mm size h. g.c.b. Chips including cost of carriage, royality etc. compl.	Sqm	9.10	410.94	₹ 3,740.00
12)	Painting Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.	Sqm	15.85	₹ 224.52	₹ 3,559.00
13)	Painting one coat with any approved primer including cost of primer per 1 Sqm	Sqm	76.41	₹ 74.06	₹ 5,659.00
14)	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm	Sqm	76.41	₹ 107.86	₹ 8,242.00
15)	Provision for M. S. Shutter	Kg	231.00	₹ 120.00	₹ 27,720.00
Total Amount for B.O.Q. =					₹ 229,411.00

(Rupees Two Lakhs Thirty Thousand Nine Hundred Fifty - Two)only


Junior Engineer,
Rairangpur Block


Assistant Executive Engineer,
Rairangpur Block


Block Development Officer,
Rairangpur Block

My quoted Rate is% (.. with in ward)
excess over/ less than/ equal to the above tendered value.

Note:-

- 1) The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate. Any conditional rate quoted is not accepted.
- 2) Strikeover on the rate quoted is liable to rejection.
- 3) Percetage rate quoted should be within 2(Two) digit after decimal point.
- 4) Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.
- 5)

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer

TENDER SCHEDULE

" CONSTRUCTION OF ADDL. CLASS ROOM AT GORUMAHISANI GOVT. PRIMARY SCHOOL "

Estimated cost	Rs 18,33,000.00
Tender amount	Rs 14,71,791.00
Earnest Money to be Deposited	Rs 14,718.00
Cost of Tender Paper	Rs 6000.00
Class of Contractor	D' & 'C'
Last Date of Receipt of Tender Paper	
Date of Opening of Tender Paper	
Time Required for Completion of work	

Abstract

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil with in 50 met initial lead and 1.5 met lift including dressing and levelling the foundation bed....etc	cum	48.19	276.89	13344.00
2	Sand filling in foundation and plinth with well watered and and ramming ..etc	Cum	86.71	974.47	84497.00
3	PCC (1:4:8) using 40 mm size CBHG metal in foundation and base including cost conveyance royalty ..etc	Cum	16.00	5956.79	95290.00
4	RCC M20 using 12mm size C.B.H.G chips etc incl cost of all materials & Labours:-	Cum	31.56	6345.25	199907.00
5	Supplying,fitting & placing uncoated HYSD bar reinforcement including all cost & carriage including labour charges,etc.	Qntl	28.40	8695.68	246522.00
6	Rigid and smooth centering ,shuttering for R.C.C. work including false works and dismantling them after casting.				
a	Plinth band	Sqm	62.64	248.85	16409.00
b	Column & Beam	Sqm	71.93	1191.58	84888.00
c	Lintel	Sqm	15.93	574.51	9152.00
d	celling beam	Sqm	16.46	574.51	9456.00
e	Chajja / Roof slab	Sqm	84.42	755.52	63777.00
7	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	Cum	13.13	4345.48	57056.00
8	Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.	Cum	27.15	4422.27	120082.00
9	6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chiping,etc.	Sqm	105.68	182.37	19273.00
10	12 mm thick cement plaster in C.M.(1:6) in external surface of wall,etc.	Sqm	125.60	195.57	24563.00

11	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall,etc.	Sqm	151.20	281.00	42487.00
13	Supplying fitting &fixing of MS Door & Window including all cost of material & Laour charges,etc.	Kg	358.15	120.00	42978.00
14	Supplying and fixing of G I pressed G I Door assembly with polymer power coated including the cost of all materials and fittings etc com.	sqm	4.41	7000.00	30870.00
15	Labour for fitting fixing of doors & windows etc	sqm	16.68	23.43	391.00
16	Fixing Vetrified tiles in floors,treads of steps and landing on 20 mm thick bed of cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labours T&P, rubbing and polishing etc all complete. (Data for 10 Sqm) (A/ R for other Bldg Items 2006, Sl.(2)	Sqm	76.60	1205.74	92359.00
17	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, Sl.(17)	Sqm	15.12	1340.37	20266.00
18	Fixing Chequred tiles in floors,treads of steps and landing on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 89, Sl.(16)	Sqm	12.42	1070.70	13298.00
19	Finishing surface of wall with Acrilic Wall Putty (Water based) of approved make and finished smooth and even surface to received painting including cost of puty all labour T&P etc complete.	Sqm	227.80	102.95	23452.00
20	Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.	Sqm	353.40	83.75	29596.00
21	Distempering two coats to wall with distemper of approved shade on new work including all cost etc complete.	Sqm	227.80	90.59	20636.00
22	Finishing wall painting two coats with any approved weather seal coat paint including all cost, carriage,royalty etc co	Sqm	125.60	107.79	13537.00
23	Painting two coat with any approved paint on Iron work over a coat of priming including all cost,carriage,royalty etc omplete.	Sqm	24.54	264.84	6499.00
24	2.5cm thick grading concrete(1:2:2) on roof slab with 4.7mm size h.g chips,etc.	Sqm	96.01	397.58	38169.00

25	Supplying, fitting and fixing of Stainless Steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipes with Balustrade of size 32mm x32mmx 2mm @ 0.90m c/c and stainless square pipe bracing of 32mm x 32mmx 2mm in three rowa in stair case as per approved design and specifications buffing, polishing including cost, carriage,royalty etc complete. (Data for 3.26 Rmt) Revised A/ R(Building) -2012, Item no. 11	Mtr	17.55	3022.09	53037.00
Total =				Rs	1471791.00

(Rupees fourteen lakhs seventy one thousand seven hundred ninety one) only.


Asst. Engineer
Rairangpur Block


Asst. Executive Engineer
Rairangpur Block


Block Development Officer
Rairangpur

Rate quoted in terms of % (percentage) less or excess over the value of the tender amount as given above (Both in words and figure in details) The Percentage less or excess will be up to two decimal point only.

- (a) In Figures% Excess/Less
- (b) In Words% Excess/Less

N.B. - Percentage of excess or Less to be quoted both in words and figures.

Singature of the Contractor

B.O.Q. FOR THE WORK :-

**Construction of ACR Building at Kapilikudar Govt. Primary School in
Daria G.P.**

Item Description	Unit	Quantity	Rate	Amount
Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm to 7cm laying in layers not exceeding 0.3m in depth etc all complete.	Cum	51.14	₹ 279.63	₹ 14,301.00
Filling in foundation and plinth with sand well watered and rammed including all cost conveyance, royalty of materials etc all complete	Cum	59.50	₹ 1,095.02	₹ 65,157.00
Cement concrete (1:3:6) with 4cm size hard granite metal including all cost conveyance, royalty of materials etc complete	Cum	17.30	₹ 6,099.09	₹ 105,508.00
R.C.C. works of M-20 grade with 20mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying including all cost conveyance, royalty of materials etc complete.	Cum	36.16	₹ 6,328.55	₹ 228,867.00
Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and Technical specification including all cost conveyance, royalty of materials etc complete.	Qtl	35.44	₹ 6,921.60	₹ 245,308.00
Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling then after casting including cost of materials complete in ground floor including all cost conveyance, royalty of materials etc complete.				
R.C.C. foundation, Plinth band and footings bases of columns mass concrete pre-cast slabs etc.	Sqm	43.45	₹ 247.80	₹ 10,766.00
R.C.C. beam, girder and dresser etc.	Sqm	75.46	₹ 1,192.53	₹ 89,986.00
R.C.C. Lintel	Sqm	19.98	₹ 571.46	₹ 11,418.00
Roof Slab & Chhaja	Sqm	85.41	₹ 754.55	₹ 64,446.00
Brick work with Fly Ash bricks having crushing strength between 100Kg/Cm ² to 149Kg/Cm ² in cement mortar (1:6) in foundation and plinth including all cost conveyance, royalty of materials etc complete				
Foundation & Plinth	Cum	10.06	₹ 5,675.77	₹ 57,100.00
Superstructure	Cum	23.03	₹ 5,708.77	₹ 131,446.00
6mm thick cement plaster (1:4) to R.C.C. surfaces finished smooth including closed deep chipping and slurry treatment including all cost conveyance & royalty etc complete.	Sqm	77.43	₹ 180.96	₹ 14,012.00
12mm cement plaster (1:6) for brick work including all cost conveyance, royalty of materials etc complete	Sqm	160.33	₹ 194.82	₹ 31,235.00
16mm thick cement plaster (1:6) over brick or stone masonry including all cost conveyance, royalty of materials etc complete	Sqm	120.99	₹ 279.65	₹ 33,834.00
Provision for M. S. Shutter	Kg	435.75	₹ 120.00	₹ 52,290.00
Labour for fitting & fixing of door & windows	Sqm	13.49	₹ 112.97	₹ 1,524.00

Providing fitting & fixing vetrified Tiles in floor of size 600mmX600mm of approved make confirming to IS:13755 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all material, labour T&P etc required for the work all complete. (Data for 10Sqm) (Vide A/R 2012 in Items of other building 1-(B) for New work of S/R-2012	Sqm	70.01	1102.79	₹ 77,205.00
Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	6.57	1598.46	10506.00
Fixing vitrified tiles in dados skirting and riser of steps on 12mm thick cement plaster 1:3 (1Cement:3Sand) jointed with neat cement slury mixed with pigment to matche shades of the tiles including rubbing and polishing completeincluding all cost conveyance, royalty of materials etc complete per 1Sqm(Details for 10Sqm)	Sqm	17.09	1341.48	22931.00
Wall painting two coat with plastic emulsion paint over a coat of primer after finising wall surface of walls with acrylic wall putty (water based) of approved make and finished smooth & even surface to received painting including cost of scaffolding charges with cost of all materials labour etc complete.				
(A) Ground Floor	Sqm	166.35	₹ 176.29	₹ 29,326.00
Priming 1 coat with any approved primer incl.cost of primer & labour all complete				
(A) Ground Floor	Sqm	358.74	₹ 74.06	₹ 26,569.00
Distempering two coats with any approved shade including cost of distemper incl all cost etc. compl.				
(A) Ground Floor	Sqm	166.35	₹ 89.69	₹ 14,920.00
Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint Per 1Sqm				
(A) Ground Floor	Sqm	112.69	₹ 107.86	₹ 12,155.00
) Painting Doors & windows two coats with any approved paint on new wood work including cost of enamel paint over a coat of primer etc all complete.				
(A) Ground Floor	Sqm	26.09	₹ 224.52	₹ 5,858.00
) 20mm Thick C.P. for grading work in C. M. (1 : 6) in roof slab including cost of carriage, roylity etc. compl.				
(A) Ground Floor	Sqm	84.10	₹ 304.71	₹ 25,626.00

Supplying, fitting and fixing of Stainless Steel of 304 grade hand railing using 50mm dia of 2mm thick circular pipes with Balustrade of size 32mm x32mmx 2mm @ 0.90m c/c and stainless square pipe bracing of 32mm x 32mmx 2mm in three rows in stair case as per approved design and specifications buffing, polishing including cost, carriage,royalty etc complete. (Data for 3.26 Rmt) Revised A/ R(Building) -2012, Item no - 11.				
(A) Ground Floor	Rmt.	12.40	₹ 3,015.75	₹ 37,395.00
			Total Amount for B.O.Q.=	₹ 1,419,689.00

(Rupees Fourteen Lakhs Ninteen Thousand Six Hundred Eighty - Nine)only

[Signature]
18/2/26
Junior Engineer,
Rairangpur Block

[Signature]
18/2/26
Assistant Executive Engineer,
Rairangpur Block

[Signature]
Block Development Officer,
Rairangpur Block

My quoted Rate is% (*write in word*)
excess over/ less than/ equal to the above tendered value.

Note:-
The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate.
Any conditional rate quoted is not accepted.
Strikeover on the rate quoted is liable to rejection.
Percentage rate quoted should be within 2(Two) digit after decimal point.
Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.

Number of correction made.....

Number of overwriting made.....

Signature of the Tenderer

TENDER SCHEDULE

" CONSTRUCTION OF MEETING-CUM-DINING HALL AT GUHALDANGRI HIGH SCHOOL

Estimated cost	Rs 10,00,000.00
Tender amount	Rs 7,73,869.00
Earnest Money to be Deposited	Rs 7739.00
Cost of Tender Paper	Rs 4000.00
Class of Contractor	D' & 'C'
Last Date of Receipt of Tender Paper	
Date of Opening of Tender Paper	
Time Required for Completion of work	

Abstract

Sl. No.	Items	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil within 50 met initial lead and 1.5 met lift including dressing and levelling the foundation bed....etc	100 cum	19.859	276.89	5416.00
2	Sand filling in foundation and plinth with well watered and and ramming ..etc	Cum	22.618	777.22	17579.00
3	PCC (1:3:6) using 40 mm size CBHG metal in foundation and base including cost conveyance royalty ..etc	Cum	4.986	29917.00	29917.00
4	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	Cum	9.438	4470.41	42190.00
5	RCC M20 using 12mm size C.B.H.G chips etc incl cost of all materials & Labours:-				
	a-Columns	Cum	3.888	6787.52	26390.00
	b-Plinth Beam	Sqm	1.500	7658.50	11488.00
	c-Column / Beam	Sqm	3.675	18330.02	67363.00
	d-Lintel Beam	Sqm	1.350	14457.43	19518.00
	e-Roof Slab	Sqm	6.336	13969.48	88516.00
6	Supplying, fitting, fixing & placing Uncoated HYSD bar reinforcement complete.	Qtl	15.07	8311.78	125295.00
7	Brick work with FLY ASH. Brick having crushing strength between 35 Kg/cm ² to 149 Kg/cm ² in C.M. (1 : 6) in super structure including cost, carriage and royalty etc.	Cum	17.18	4470.41	76779.00

8	25mm thick greading concrete (1:2:2) on roof slab with 6 mm size hbg chips for new work	Sqm	52.14	399.51	20831.00
9	6 mm thick Cement Plaster with C.M (1:4) on ceiling including all cost, conveyance & royalty etc. complete. A/R, Page-109, SI - (26)	Sqm	92.17	182.46	16816.00
10	16 mm thick Cement Plaster with CM (1:6) including all cost, conveyance & royalty etc. complete.	Sqm	95.58	280.74	26834.00
11	12 mm thick CP with CM (1:6) including all cost, conveyance & royalty etc all complete. A/R, Page-103, SI - (4)	sqm	104.40	195.35	20395.00
12	Supplying fitting fixing of M S door & window ...etc	Kg	705.00	103.30	72828.00
13	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, SI.(17)	Sqm	40.60	1208.36	49060.00
14	Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. (Data for 10 Sqm) A/ R Page - 90, SI.(17)	Sqm	5.45	1344.01	7318.00
15	Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.	Sqm	292.15	83.75	24467.00
16	Distempering two coats to wall with distemper of approved shade on new work including all cost etc complete.	Sqm	95.58	90.59	8658.00
17	Finishing wall painting two coats with any approved weather seal coat paint including all cost, carriage,royalty etc co	Sqm	104.40	107.79	11253.00
18	Painting two coat with any approved paint on Iron work over a coat of priming including all cost,carriage,royalty etc omplete.	Sqm	18.72	264.84	4958.00

19	Total =		Rs	773869.00
----	---------	--	----	-----------

(Rupees seven lakhs seventy three thousand eight hundred sixty nine) only.


Asst. Engineer
Rairangpur Block


Asst. Executive Engineer
Rairangpur Block


Block Development Officer
Rairangpur

Rate quoted in terms of % (percentage) less or excess over the value of the tender amount as given above (Both in words and figure in details) The Percentage less or excess will be up to two decimal point only.

- (a) In Figures% Excess/Less
 (b) In Words% Excess/Less

N.B. - Percentage of excess or Less to be quoted both in words and figures.

Singature of the Contractor